

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	99-1-N	WILL	52	4
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

Contract 62834

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	URBAN 100% STATE 1000-2A	TRAFFIC SIGNALS 100% STATE 10031-1F	MONEE F.P.D. 100% 10031-3D	
* 87200400	SPAN WIRE	FOOT	870		870		
* 87200500	TETHER WIRE	FOOT	870		870		
* 87302225	ELECTRIC CABLE AERIAL SUSPENDED, SIGNAL, NO. 14 3C	FOOT	630		630		
* 87302245	ELECTRIC CABLE AERIAL SUSPENDED, SIGNAL, NO. 14 5C	FOOT	1765		1765		
* 87302255	ELECTRIC CABLE AERIAL SUSPENDED, SIGNAL, NO. 14 7C	FOOT	210		210		
* 87302505	ELECTRIC CABLE AERIAL SUSPENDED, SERVICE, NO. 6 2 C	FOOT	150		150		
* 88700200	LIGHT DETECTOR	EACH	4			4	
* 88700300	LIGHT DETECTOR AMPLIFIER	EACH	2			2	
X0300626	CURB AND GUTTER REMOVAL	FOOT	280	280			
X0329907	PORTLAND CEMENT CONCRETE SURFACE REMOVAL 2 1/2"	SQ YD	213	213			
X3550500	BITUMINOUS BASE COURSE SUPERPAVE 8"	SQ YD	291	291			
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	2	2			
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	28	28			
X4066548	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "F", N90	TON	1031	1031			
X4066558	POLYMERIZED BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N90	TON	1139	1139			
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50	TON	440	440			
X7030130	PAVEMENT MARKING TAPE, TYPE III 4", SPECIAL	FOOT	9406	9406			
* X8730350	ELECTRIC CABLE AERIAL SUSPENDED NO. 20 3/C, TWISTED, SHIELDED	FOOT	700			700	
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	2394	2394			
* XX005723	VIDEO DETECTION SYSTEM (COMPLETE INTERSECTION)	EACH	2		2		
* X8800025	SIGNAL HEAD, L.E.D., 1-FACE, 3 SECTION, SPAN WIRE MOUNTED	EACH	14		14		
* X8800046	SIGNAL HEAD, L.E.D., 1-FACE, 5 SECTION, SPAN WIRE MOUNTED	EACH	4		4		
* X0325134	WIRELESS INTERCONNECT (COMPLETE)	EACH	1		1		

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	URBAN 100% STATE 1000-2A	TRAFFIC SIGNALS 100% STATE 10031-1F	MONEE F.P.D. 100% 10031-3D	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52			
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1			
* X8050015	SERVICE INSTALLATION, POLE MOUNT	EACH	1		1		
* 86000100	MASTER CONTROLLER	EACH	1		1		
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	3	3			
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2			
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	5	5			
60107600	PIPE UNDERDRAINS, 4"	FOOT	320	320			
X0325167	POROUS GRANULAR EMBANKMENT, SUBGRADE 24"	SQ YD	50	50			

*SPECIALTY ITEMS.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

Rev.

PLOT DATE: 9/20/2005