

INDEX OF SHEETS

SHEET NO.	TITLE
1	COVER SHEET
2	INDEX OF SHEETS, INDEX OF STATE STANDARDS, GENERAL NOTES, CALENDAR OF CONSTRUCTION WORK & COMMITMENTS
3	SUMMARY OF QUANTITIES
4 - 5	CORNER GARDEN AT 79TH STREET AND LAFAYETTE AVENUE - PLAN AND DETAIL
6 - 7	CORNER GARDEN AT 87TH STREET AND LAFAYETTE AVENUE - PLAN AND DETAIL
8 - 11	PLANTING BED AT LAFAYETTE AVENUE NORTH OF 95TH STREET- PLAN, DETAIL, AND SCHEDULE OF LANDSCAPE ITEMS
12 - 14	PLANTING BED AT LAFAYETTE AVENUE SOUTH OF 95TH STREET- PLAN, DETAIL, AND SCHEDULE OF LANDSCAPE ITEMS
15 - 16	PLANTING BEDS - LANDSCAPING PLAN DETAIL
17	PLANTING BEDS - STANDARD METER VAULTS, WATER SERVICE INSTALLATION, PAVEMENT REMOVAL AND REPLACEMENT DETAILS
18	CORNER GARDEN AND PLANTING BED - UTILITY DROP DOWN DETAIL
19	CONCRETE MEDIAN SURFACE, 5" (MODIFIED) - WITH CALIFORNIA FINISH DETAIL
20 - 23	SUGGESTED CONSTRUCTION SEQUENCE - CONTRACT #62695 (17B) (FOR INFORMATION ONLY)
24 - 27	MAINTENANCE OF TRAFFIC PLAN FROM CONTRACT #62695 (17B) - 79TH STREET, 87TH STREET, NORTH OF 95TH STREET AND SOUTH OF 95TH STREET (FOR INFORMATION ONLY)
28	BD-22 DIST 1, PAVEMENT PATCHING FOR BITUMINOUS SURFACED PAVEMENT
29	TC-10 DIST 1, TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS
30	TC-22 DIST 1, TEMPORARY INFORMATION SIGNING

INDEX OF STATE STANDARDS

STANDARD NO.	TITLE
000001-04	STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
606001-02	CONCRETE CURB AND COMBINATION CONCRETE CURB AND GUTTER
701601-04	URBAN LANE CLOSURE, MULTILANE 1W OR 2W WITH NONTRAVERSABLE MEDIAN
701701-04	URBAN LANE CLOSURE MULTILANE INTERSECTION
701801-03	LANE CLOSURE MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE
702001-05	TRAFFIC CONTROL DEVICES

GENERAL NOTES:

- THE CONTRACTOR SHALL NOT SET UP A YARD OR FIELD OFFICE ON IDOT PROPERTY WITHOUT WRITTEN PERMISSION FROM IDOT.
- THE CONTRACTOR SHALL TAKE ALL NECESSARY SAFETY PRECAUTIONS TO PROTECT AND PROVIDE ACCESS TO ABUTTING PROPERTY, UTILITIES, PEDESTRIANS, AND VEHICULAR TRAFFIC.
- NIGHT OPERATIONS: WHEN ARTIFICIAL LIGHTING IS UTILIZED IN NIGHT OPERATIONS, THE CONTRACTOR SHALL EXERCISE THE UTMOST PRECAUTION IN PREVENTING ADVERSE VISIBILITY TO THE MOTORING PUBLIC AS WELL AS THE ADJOINING RESIDENTIAL AREAS.
- ALL ELEVATIONS SHOWN ARE BASED ON THE CHICAGO CITY DATUM OF 0.00, WHICH IS 579.19 FEET ABOVE MEAN TIDE NEW YORK. (NAVD 88)
- ANY DAMAGE DONE TO EXISTING ITEMS BY THE CONTRACTOR SHALL BE REPAIRED BY THE CONTRACTOR AT THE CONTRACTOR'S OWN EXPENSE.
- THIS CONTRACT INCLUDES THE INSTALLATION OF PLANTING BEDS AND CORNER GARDENS AT INDICATED RETAINING WALLS. THE RETAINING WALLS ARE CONSTRUCTED IN CONTRACT #62695 (17B).
- THE TRAFFIC CONTROL DEVICES SHOWN AS PROVIDED UNDER CONTRACT #62695 ("FOR INFORMATION ONLY" - MAINTENANCE OF TRAFFIC SHEETS) MAY PROTECT THIS CONTRACT'S WORK AREA. IF WORK ON CONTRACT #62695 HAS BEEN COMPLETED PRIOR TO OR DURING THIS CONTRACT'S WORK, THE CONTRACTOR MUST PROVIDE ALL NECESSARY TRAFFIC CONTROL DEVICES NEEDED TO COMPLETE THE WORK. THIS WORK SHALL BE INCLUDED IN THE COST OF TRAFFIC CONTROL AND PROTECTION (SPECIAL).
- PLANS FOR THE WATER SERVICE CONNECTIONS FOR IRRIGATION SYSTEMS SHOULD BE SUBMITTED FOR REVIEW AND APPROVAL TO:

MR. JOHN FLYNN
DEPARTMENT OF CONSTRUCTION AND PERMITS
ROOM 906, CITY HALL
121 NORTH LASALLE STREET
CHICAGO, ILLINOIS 60602
- THE ENGINEER SHALL BE ALLOWED ACCESS TO THE FIELD OFFICE IN USE FOR CONTRACT #62695.
- THE CONTRACTOR MUST OBTAIN ALL NECESSARY PERMITS FROM THE CITY OF CHICAGO AND THE STATE OF ILLINOIS PRIOR TO COMMENCING CONSTRUCTION. THE COSTS MUST BE INCLUDED IN THE CONTRACT.
- PAYMENTS FOR ADJUSTMENTS TO WATER VALVE VAULTS SHALL NOT BE MADE TO THE CONTRACTOR UNTIL THIS WORK HAS BEEN INSPECTED AND APPROVED BY THE CITY OF CHICAGO DEPARTMENT OF WATER MANAGEMENT.
- PERMITS FROM THE DEPARTMENT OF WATER MANAGEMENT ARE REQUIRED FOR ALL WORK INVOLVING ADJUSTMENT OF STRUCTURES. THE DEPARTMENT OF WATER MANAGEMENT'S PERMIT MUST BE OBTAINED BY A LICENSED SEWER DRAIN LAYER PRIOR TO START OF CONSTRUCTION. THE LICENSED SEWER CONTRACTOR/ SUBCONTRACTOR MUST SUBMIT TWO SETS OF PLANS APPROVED BY THE DEPARTMENT OF WATER MANAGEMENT FOR THE ISSUANCE OF THE SEWER PERMIT TO BUREAU OF ENGINEERING SERVICES-SEWER SECTION, JARDINE PURIFICATION PLANT, EL+51, ROOM 313, 1000 E. OHIO ST., CHICAGO, IL 60611. INSPECTION WILL BE PROVIDED BY THE DEPARTMENT OF WATER MANAGEMENT.
- CITY OF CHICAGO WATER VALVE VAULTS AND SEWER STRUCTURES SHALL NOT BE CLOSED, COVERED, OR OTHERWISE OBSTRUCTED DURING CONSTRUCTION WITHOUT WRITTEN PERMISSION FROM THE CITY OF CHICAGO DEPARTMENT OF WATER MANAGEMENT.
- THE RESIDENT ENGINEER AND THE CONTRACTOR SHALL FIELD VERIFY THE CITY'S EXISTING SEWER FACILITIES IN THE LIMITS OF THE REFERENCED PROJECT FOR ANY CONFLICTS DUE TO THE PROPOSED IMPROVEMENT. ANY CONFLICT SHOULD BE RESOLVED WITH THE DEPARTMENT OF WATER MANAGEMENT PRIOR TO START OF CONSTRUCTION.
- IT IS CALLED TO THE CONTRACTOR'S ATTENTION THAT HE/SHE WILL BE REQUIRED TO PAY FOR ANY INSPECTION OR PERMIT FEES TO THE VARIOUS DEPARTMENTS OF THE CITY OF CHICAGO. THE COST FOR THESE FEES WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED INCLUDED IN THIS CONTRACT. PERMIT FEES MUST BE PAID PRIOR TO COMMENCING CONSTRUCTION.

CALENDAR OF CONSTRUCTION WORK

PHASE	YEAR	WORK DATES		CONSTRUCTION WORK
		FROM	TO	
PHASE I	2006	MAY 1	AUG. 15	INSTALLATION OF CONCRETE CURB (NORTH AND SOUTH OF 95TH STREET), CONCRETE MEDIAN SURFACE (NORTH AND SOUTH OF 95TH STREET), AND UTILITY DROP DOWNS (NORTH AND SOUTH OF 95TH STREET AND 87TH STREET). EXCAVATION AND PLACEMENT OF POROUS GRANULAR MATERIAL, PLANTING MIX, AND SEEDING/MULCH (ALL GARDENS). INSTALLATION OF WATER SYSTEM ITEMS AND IRRIGATION SYSTEM (NORTH AND SOUTH OF 95TH STREET).
		MAY 1	SEPT. 15	INSTALLATION OF ALL WOODY PLANTS. WOODY PLANTS MUST BE CONTAINER OR DUG WHILE DORMANT AND MAINTAINED PROPERLY UNTIL PLANTED. ALL WOODY PLANTS MUST BE INSTALLED PRIOR TO PERENNIALS.
		AUG. 15	SEPT. 15	INSTALL PERENNIAL PLANTS AFTER ALL WOODY PLANTS HAVE BEEN INSTALLED.
		OCT. 15	NOV. 15	INSTALL BULBS.
		OCT. 15		CERTIFICATION TO THE BUREAU OF MAINTENANCE THAT ALL PLANTS HAVE BEEN INSTALLED AND ARE IN A LIVE HEALTHY CONDITION AND ELIGIBLE FOR A MAY 1 - MAY 7, 2007 PERIOD OF ESTABLISHMENT INSPECTION.
PHASE I	2006			
PHASE	YEAR	WORK DATES		CONSTRUCTION WORK
		FROM	TO	
PHASE II	2007	MARCH 1	APRIL 30	PERIOD OF ESTABLISHMENT PLANT CARE REQUIRED FOR ALL PLANTS. (WEEDING, WATERING, OR OTHER WORK WHICH IS NECESSARY TO MAINTAIN HEALTH AND SATISFACTORY APPEARANCE OF THE PLANTING IS INCLUDED IN THE COST OF THE CONTRACT).
		MAY 1	MAY 7	PERIOD OF ESTABLISHMENT INSPECTION.
		MAY 8	MAY 31	INSTALLATION OF ALL REQUIRED REPLACEMENT PLANTS, AND ALL REQUIRED CLEAN UP OF ALL PLANT BEDS SHALL BE COMPLETED BY THIS DATE.
PHASE II	2007	MAY 31		COMPLETION DATE
	2007	JUNE 15		FINAL INSPECTION DATE

COMMITMENTS:

NONE

TYLIN INTERNATIONAL

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94 (DAN RYAN EXPRESSWAY)
INDEX OF SHEETS, INDEX OF STATE STANDARDS, GENERAL NOTES CALENDAR OF CONSTRUCTION WORK & COMMITMENTS
 SCALE: NONE DRAWN BY: JDF
 DATE: SEPTEMBER 2, 2005 CHECKED BY: RTM

8/31/2005 3:06:40 PM