

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
513	1168-4	DEKALB	416	4
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CODE NUMBER	PAY ITEMS	UNIT	80% FED / 20% STATE TOTAL QUANTITY I 000-2A
4400007	BITUMINOUS SURFACE REMOVAL 2"	SQ YD	5,245
4400030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	6,540
44000100	PAVEMENT REMOVAL	SQ YD	23,242
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	610
44000300	CURB REMOVAL	FOOT	2,786
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	3,391
44000600	SIDEWALK REMOVAL	SQ FT	44,315
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	182
44004300	PAVEMENT BREAKING	SQ YD	389
44200998	CLASS B PATCHES, TYPE III, 12 INCH	SQ YD	43
44213200	SAW CUTS	FOOT	137
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	14,207
48100100	AGGREGATE SHOULDERS, TYPE A	TON	748
48202400	BITUMINOUS SHOULDERS SUPERPAVE 6"	SQ YD	2,749
50100200	REMOVAL OF EXISTING STRUCTURES	L SUM	1
50104400	CONCRETE HEADWALL REMOVAL	EACH	2
50105210	REMOVE EXISTING CULVERTS	FOOT	110
50300225	CONCRETE STRUCTURES	CU YD	6
50800105	REINFORCEMENT BARS	POUND	485
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	70
51000105	PIPE HANDRAIL	FOOT	62
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTION 30"	EACH	1
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTION 36"	EACH	2
54213687	PRECAST REINFORCED CONCRETE FLARED END SECTION 42"	EACH	1
54215550	METAL END SECTIONS 15"	EACH	6
54215565	METAL END SECTIONS 30"	EACH	1
54244405	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	EACH	3
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	382
542D0235	PIPE CULVERTS, CLASS D, TYPE 1 30"	FOOT	20
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	96
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	348
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	70
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	1,148
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	1,002
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	733

PLOT DATE = Wed Sep 14 13:05:52 2005
 FILE NAME = C:\projects\62507280\62507280.dgn
 PLOT SCALE = 1/8" = 1'-0"
 USER NAME = jordanhd

REVISION
 10-31-05