

F.A.P. RTR	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
-5C3	J168-4	DEKALB	416	5
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CODE NUMBER	PAY ITEMS	UNIT	80% FED / 20% STATE TOTAL QUANTITY 1 000-2A
550A2320	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 12"	FOOT	77
550A2520	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 12"	FOOT	833
550A2560	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 24"	FOOT	896
550A2580	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 30"	FOOT	203
56300100	ADJUSTING SANITARY SEWERS, 8-INCH DIAMETER OR LESS	FOOT	600
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	15
60107600	PIPE UNDERDRAINS 4"	FOOT	1,194
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	8
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	19
60222930	MANHOLES, TYPE A, 5'-DIAMETER, WITH SPECIAL FRAME AND GRATE	EACH	2
60228110	MANHOLES, SANITARY, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3
60228400	MANHOLES, SPECIAL	EACH	1
60240385	INLETS, TYPE B, WITH SPECIAL FRAME AND GRATE	EACH	15
60242400	INLETS, SPECIAL	EACH	27
60242700	INLETS, SPECIAL, NO. 3	EACH	20
60242800	INLETS, SPECIAL, NO. 4	EACH	1
60242801	INLETS, SPECIAL, NO. 5	EACH	59
60255500	MANHOLES TO BE ADJUSTED	EACH	16
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	23
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	15
60500040	REMOVING MANHOLES	EACH	34
60500050	REMOVING CATCH BASINS	EACH	5
60500060	REMOVING INLETS	EACH	27
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	8.3
60600605	CONCRETE CURB, TYPE B	FOOT	2,605
60600705	CONCRETE CURB, TYPE B (ABUTTING EXISTING PAVEMENT)	FOOT	60
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	410
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	20,301
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	85
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	16
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	176
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	2
61140000	STORM SEWERS, SPECIAL 8"	FOOT	100
61140100	STORM SEWERS, SPECIAL 10"	FOOT	100
61140200	STORM SEWERS, SPECIAL 12"	FOOT	100
* 63000000	STEEL PLATE BEAM GUARDRAIL TYPE A	FOOT	188
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2

PLOT DATE = Wed Sep 14 15:05:14 2005
 PLOT SCALE = 30.0000 / 1 IN.
 USER NAME = jordanhd