

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	129K	WINNEBAGO	585	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

PAY CODE NO.	PAY ITEM	UNIT	URBAN TOTAL QUANTITY	80% FEDERAL 20% STATE 1000-2A (IL 173)	45% STATE 55% TOLLWAY 1000-2A (I-90)	100% STATE 1000-2A (RAMPS)	45% STATE 55% TOLLWAY X781-2A STRUCTURES SN 101-9963/SN 101-9964	80% FEDERAL 20% STATE Y030-1E	80% FEDERAL 20% STATE Y031-1F	80% FEDERAL 20% STATE SFTY-3N	80% FEDERAL 20% STATE BIKE / PED. FACILITY Y046	100% HARLEM ROSCOE FIRE DISTRICT Y031-3D
X7013015	TRAFFIC CONTROL FOR ROAD CLOSURE	L SUM	1	1								
* X8801300	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	10						10			
* X8801310	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	20						20			
* X8801395	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	4						4			
* X8801400	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	3						3			
* X8801415	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	10						10			
* X8801437	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3-SECTION, 1-5-SECTION, BRACKET MOUNTED	EACH	1						1			
* X8801447	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1						1			
* XX003163	EMERGENCY VEHICLE PRIORITY SYSTEM	EACH	3									3
XX004346	BARRIER DELINEATOR	EACH	91		91							
X0325103	TEMPORARY PAVEMENT, SUPERPAVE, 8"	SQ YD	1209	1209								
* XX005296	STEEL CASING PIPE 36"	FOOT	455			455						
* XX005372	POLYUREA PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	561	308		253						
X0325104	SLOPED HEADWALL, TYPE 1, 24"	EACH	1		1							
* XX006058	POLYUREA PAVEMENT MARKING - LINE 4"	FOOT	33277	30433		1834					1010	
* XX006059	POLYUREA PAVEMENT MARKING - LINE 6"	FOOT	3218	2257		961						
* XX006060	POLYUREA PAVEMENT MARKING - LINE 12"	FOOT	2508	2508								
* XX006061	POLYUREA PAVEMENT MARKING - LINE 24"	FOOT	499	400		99						
X0325117	CATCH BASIN TYPE B WITH FRAME AND GRATE	EACH	3		1	2						
X0325118	CATCH BASIN TYPE G-2 WITH TYPE G-2 FRAME & GRATE	EACH	16		2	14						
X0325119	CATCH BASIN TYPE G-3 WITH TYPE G-3 FRAME & GRATE	EACH	25		25							
X0325120	GUTTER TYPE G-2	FOOT	3734		372	3362						
X0325121	GUTTER TYPE G-3	FOOT	6211		6211							
X0325122	HEADWALL, TYPE 4	EACH	4			4						
* X0325124	EPOXY PAVEMENT MARKING - LINE 10"	FOOT	6930		6706	224						
X0325125	SLOPED HEADWALL, TYPE 1, 12"	EACH	52		28	24						
X0325126	SLOPED HEADWALL, TYPE 1, 15"	EACH	4		2	2						
X0325127	SLOPED HEADWALL, TYPE 1, 18"	EACH	4		4							
X0325128	SLOPE DRAIN INLET	EACH	12		10	2						
X0325129	TEMPORARY SHOULDERS, 8 INCH	SQ YD	71	71								
X0325130	HEADWALL, TYPE 1, 24"	EACH	2			2						
X0325131	HEADWALL, TYPE 1, 30"	EACH	2		2							
X0325132	SHOULDER RUMBLE STRIP REMOVAL	SQ YD	7022		7022							
X0325133	ANCHOR INSTALLATION, TYPE 2	EACH	6		6							
X0325134	ANCHOR INSTALLATION, TYPE 4	EACH	1		1							
X0325135	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW, TEST LEVEL 3, SPECIAL)	EACH	2						2			
X0325136	CATCH BASIN TYPE M-2 WITH FRAME AND GRATE	EACH	1		1							
X0325137	MANHOLES, TYPE 1, 4' DIAMETER WITH TYPE 1 FRAME AND COVER RESTRICTOR	EACH	2		1	1						
X0325138	P.C.C. RAMPED MEDIAN TERMINAL SPECIAL	SQ YD	103	103								
* X0325139	POLYUREA PAVEMENT MARKING - LINE 8"	FOOT	4145	4105		40						
X0325140	MANHOLES, TYPE 1, 4' DIA. WITH FRAME AND COVER	EACH	7		7							
X0325141	SLOPED HEADWALL TYPE 3, 6"	EACH	7		3	4						



100% NORTH PARK PUBLIC WATER DISTRICT

REVISED 11-2-05

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. N/A
 HORIZ. N/A
 DATE: OCTOBER 4, 2005

DRAWN BY: KRL
 CHECKED BY: PDS