

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	129K	WINNEBAGO	585	58
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

EARTHWORK SCHEDULE

				EXCAVATION / EMBANKMENT					
				21101505	20200100	20200410	20201200	20400800	20300100
				TOPSOIL EXCAVATION AND PLACEMENT	EARTH EXCAVATION	EARTH EXCAVATION (SPECIAL)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	FURNISHED EXCAVATION	CHANNEL EXCAVATION
STATION	OFF	STATION	OFF	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD
IL 173									
142+32.87		156+00.00			4183		7910		
148+86.62	115.74' LT								20
156+00.00		170+00.00			4644		4589		
160+48.30	92.7' RT					19			
170+00.00		184+00.00			5726		3069		
184+00.00		196+50.00			43634		5620		
196+50.00		198+00.00			6591		1256		
198+00.00		212+00.00			48071		11951		
212+00.00		213+00.00			1610		657		
213+00.00		226+00.00			5833		3126		
226+00.00		231+00.00			2521		1595		
I-90									
410+96.78		483+00.00			32826		17991		
RAMP A									
800+00.00		806+46.60					2705		
800+00.00		831+73.75			32432				
806+46.60		831+73.75		13282					
RAMP B									
5001+00.00		5025+81.91		9591	774				
5023+00.00		5025+00.00					1889		
RAMP C									
4001+00.00		4019+75.00			6151		9602		
RAMP D									
1300+00.00		1320+53.95			104705		13956		
LYFORD ROAD									
2001+00.00		2007+00.00			10239		3431		
2007+00.00		2010+00.00			565		617		
LYFORD ROAD NORTH									
12+00.00		17+00.00			126		209		
17+00.00		19+90.71			13		10		
BIKEPATH									
557+68.92		570+00.00			222				
570+00.00		585+00.00			278				
585+00.00		591+99.99			141				
CENTER POND									
5999+73.80		6012+92.29		32453	51700		1324	396	
TOTAL				55326	362985	19	91507	396	20

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. N/A
 HORIZ. N/A
 DATE: OCTOBER 30, 2005

DRAWN BY: KRL
 CHECKED BY: PDS

REVISED
 11-2-05
SHEET