

# SUMMARY OF QUANTITIES

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
203	9BR-4	ROCK ISLAND	21	2
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	X080-2A 80 % FED 20 % STATE	
20200100	EARTH EXCAVATION	CU YD	52	52	
20400800	FURNISHED EXCAVATION	CU YD	83	83	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	142	142	
25100630	EROSION CONTROL BLANKET	SO YD	4166	4166	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	20	20	
28000400	PERIMETER EROSION BARRIER	FOOT	588	588	
28000500	INLET AND PIPE PROTECTION	EACH	1	1	
44000007	BITUMINOUS SURFACE REMOVAL 2"	SO YD	116	116	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	220	220	
50101500	REMOVAL OF EXISTING SUPER STRUCTURES	EACH	1	1	
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SO FT	1411	1411	
50901005	STEEL BRIDGE RAIL, TYPE SM	FOOT	158	158	
51500100	NAME PLATES	EACH	1	1	
54213450	END SECTION 15	EACH	2	2	
54213465	END SECTION 30	EACH	2	2	
54200220	PIPE CULVERTS, CLASS D, TYPE 1, 15"	FOOT	90	90	
54200235	PIPE CULVERTS, CLASS D, TYPE 1, 30"	FOOT	124	124	
58100200	WATERPROOFING MEMBRANE SYSTEM	SO YD	158	158	

PLOT DATE = Fri Sep 02 11:46:59 2005  
 PLOT SCALE = 1/8" = 100'-0"  
 USER NAME = rjones