

SCHEDULE OF QUANTITIES

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
203	9BR-4	ROCK ISLAND	21	6
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

20200100	EARTH EXCAVATION CU YD LOCATION 14 91+ 15.47 - 92+ 51.59 LT & RT 38 93+ 34.11 - 93+ 71.95 LT & RT 52 TOTAL	63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A EACH LOCATION 1 92+ 17.67 - 92+ 51.43 RT 1 92+ 17.84 - 92+ 51.59 LT 1 93+ 34.11 - 93+ 59.41 RT 1 93+ 34.13 - 93+ 62.27 LT 4 TOTAL
20400800	FURNISHED EXCAVATION CU YD LOCATION 83 91+ 0 - 92+ 25 LT & RT 83 TOTAL	63100167	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT) EACH LOCATION 1 91+ 55.35 - 92+ 5.2 LT 1 93+ 59.41 - 93+ 49 RT 1 93+ 62.27 - 93+ 67.52 LT 3 TOTAL
21101615	TOPSOIL FURNISH AND PLACE 4" SQ YD LOCATION 58 91+ 0 - 92+ 51.59 LT & RT 84 93+ 34.08 - 93+ 71.95 LT & RT 142 TOTAL	63100169	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (FLARED) EACH LOCATION 1 91+ 67.71 - 92+ 17.58 RT 1 TOTAL
28000250	TEMPORARY EROSION CONTROL SEEDING POUND LOCATION 10 90+ 89.89 - 92+ 51.59 LT & RT 10 93+ 34.08 - 93+ 71.95 LT & RT 20 TOTAL	63200310	GUARDRAIL REMOVAL FOOT LOCATION 97 91+ 54.81 - 92+ 51.56 LT 97 91+ 64.94 - 92+ 51.31 RT 36 93+ 34.07 - 93+ 59.43 RT 58 93+ 34.13 - 93+ 66.89 LT 288 TOTAL
28000400	PERIMETER EROSION BARRIER FOOT LOCATION 340 90+ 78.38 - 92+ 71.1 LT & RT 248 93+ 29.4 - 93+ 71.95 LT & RT 588 TOTAL	63500105	DELINEATORS EACH LOCATION 1 91+ 55.35 LT 1 91+ 67.71 RT 1 93+ 49 RT 1 93+ 67.52 LT 4 TOTAL
28000500	INLET AND PIPE PROTECTION EACH LOCATION 1 90+ 91.99 LT 1 TOTAL	78001110	PAINT PAVEMENT MARKING LINE 4" FOOT LOCATION 70 92+ 31.48 - 93+ 54.12 SKIP DASH - 2 COATS 490 92+ 31.48 - 93+ 54.12 WHITE EDGELINES - 2 COATS 560 TOTAL
44000007	BITUMINOUS CONCRETE SURFACE REMOVAL 2" SQ YD LOCATION 58 92+ 31.48 - 92+ 51.39 58 93+ 34.08 - 93+ 54.12 116 TOTAL	78100100	RAISED REFLECTIVE PAVEMENT MARKER EACH LOCATION 2 92+ 31.48 - 93+ 54.12 2 TOTAL
48101200	AGGREGATE SHOULDERS, TYPE B TON LOCATION 33 91+ 15.47 - 92+ 51.59 LT 29 91+ 64.55 92+ 51.33 RT 35 93+ 34.15 93+ 71.95 LT 43 93+ 34.09 - 93+ 41.63 RT 80 GOOD NEIGHBOR POLICY 220 TOTAL	78200410	GUARDRAIL MARKERS, TYPE A EACH LOCATION 4 91+ 55.35 - 92+ 51.59 LT 4 91+ 67.71 - 92+ 51.43 RT 4 93+ 34.11 - 93+ 49 RT 4 93+ 34.13 - 93+ 67.52 LT 16 TOTAL
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15" FOOT LOCATION 90 91+ 70.25 - 92+ 59.54 RT 90 TOTAL	78201000	TERMINAL MARKER - DIRECT APPLIED EACH LOCATION 1 91+ 55.35 LT 1 91+ 67.71 RT 1 93+ 49 RT 1 93+ 67.52 LT 4 TOTAL
542D0235	PIPE CULVERTS, CLASS D, TYPE 1 30" FOOT LOCATION 124 90+ 91.96 - 92+ 14.92 LT 124 TOTAL	X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX C, N50 TON LOCATION 10 92+ 31.48 - 92+ 51.39 10 93+ 34.08 - 93+ 54.12 50 GOOD NEIGHBOR POLICY 25 BRIDGE 95 TOTAL
54213450	END SECTIONS 15" EACH LOCATION 1 92+ 51.05 RT 1 TOTAL		
54213465	END SECTIONS 30" EACH LOCATION 1 90+ 91.99 LT 1 92+ 14.92 LT 2 TOTAL		
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A FOOT LOCATION 12.5 92+ 5.2 - 92+ 17.7 LT 12.5 TOTAL		

PLOT DATE = Fri, Sep 02 11:46:59 2025
 PLOT SCALE = 50.0000' x 11.0000' (vertical)
 USER NAME = rjn