

SUMMARY OF QUANTITIES

F.A.P. RITE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
68	298R-1	DEKALB	25	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

CODE NUMBER	ITEM	UNIT	80% FED 20% STATE		SFTY-3N
			TOTAL QUANTITY	X080-2A 80% FED/ 20% STATE	
20200100	EARTH EXCAVATION	CU YD	20	20	
20400800	FURNISHED EXCAVATION	CU YD	10	10	
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	241	241	
42001300	PROTECTIVE COAT	SQ YD	266	266	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	72	72	
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1	1	
50300260	BRIDGE DECK GROOVING	SQ YD	249	249	
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	254	254	
50301245	FORMED CONCRETE REPAIR (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	187	187	
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	2380	2380	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3130	3130	
50901005	STEEL BRIDGE RAIL, TYPE SM	FOOT	109	109	
51500100	NAME PLATES	EACH	1	1	
59000100	EPOXY CRACK SEALING	FOOT	117	117	
63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4	
63200310	GUARDRAIL REMOVAL	FOOT	174	174	
63301210	REMOVE AND RE - ERECT STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	75	75	
63500105	DELINEATORS	EACH	3	3	
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2	2	
67000400	ENGINEERS FIELD OFFICE, TYPE A	CAL MO	3	3	
67100100	MOBILIZATION	L SUM	1	1	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	588	588	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	516	516	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2276	2276	
78200410	GUARDRAIL MARKERS, TYPE A	EACH	16	16	
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2	
78300500	PAINT PAVEMENT MARKING REMOVAL	SQ FT	340	340	
X4066424	BITUMINOUS SURFACE COURSE, SUPERPAVE, MIX "D", N50	TON	63	63	
X6330103	REMOVE AND RE - ERECT TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL, TANGENT	EACH	1	1	
X6330104	REMOVE AND RE - ERECT TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL, FLARED	EACH	2	2	
Z0002600	BAR SPLICERS	EACH	55	55	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON - REDIRECTIVE), TEST LEVEL 3	EACH	2		2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON - REDIRECTIVE), TEST LEVEL 3	EACH	2		2

* SPECIALTY ITEMS

PLOT DATE = Wed Aug 24 10:38:01 2005
 FILE NAME = c:\projects\2005\64\64s104\64s104.dgn
 USER = mgj17