

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
553	119BR-3	OGLE	40	2
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	X080-2A 80 % FED 20 % STATE	SFTY-3N 80 % FED 20 % STATE
20200100	EARTH EXCAVATION	CU YD	44	44	
20400800	FURNISHED EXCAVATION	CU YD	202	202	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	738	738	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	150	150	
25100630	EROSION CONTROL BLANKET	SO YD	855	855	
28000400	PERIMETER EROSION BARRIER	FOOT	906	906	
44000007	BITUMINOUS CONCRETE SURFACE REMOVAL 2"	SO YD	142	142	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	200	200	
48202050	BITUMINOUS SHOULDERS SUPERPAVE 2"	SO YD	24	24	
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1	1	
50300260	BRIDGE DECK GROOVING	SO YD	323	323	
50300300	PROTECTIVE COAT	SO YD	399	399	
50301200	CONCRETE WEARING SURFACE	SO YD	333	333	
50301245	FORMED CONCRETE REPAIR (LESS THAN 5 INCHES)	SO FT	10	10	
50301250	FORMED CONCRETE REPAIR (GREATER THAN 5 INCHES)	SO FT	6	6	
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SO. FT.	3155	3155	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	4560	4560	
50901005	STEEL BRIDGE RAIL, TYPE SM	FOOT	273	273	
51500100	NAME PLATES	EACH	1	1	
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4	
* 63100169	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	EACH	1	1	
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	3	3	
63200310	GUARDRAIL REMOVAL	FOOT	325	325	
63301210	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	875	875	
63500105	DELINEATORS	EACH	4	4	

* SPECIALTY ITEMS

PLOT DATE = Fri Sep 02 11:41:05 2005
 PLOT SCALE = 5000000 / IN.
 USER NAME = mag111

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. DATE HORIZ. DRAWN BY CHECKED BY

SUMMARY OF QUANTITIES