CONTRACT NO. 64A47

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
553	119BR-3	OGLE	40	7
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SCHEDULE OF QUANTITIES

20200100 EARTH EXCAVATION

CU YD	LOCATION					
22		1524 +	29 -	1531 +	17	RT
22		1524 +	89 -	1532 +	16	LT
44	TOTAL					

21101615 TOPSOIL FURNISH AND PLACE, 4"

SQ YD	LOCATION					
369		1524 +	29 -	1531 +	17	RT
369		1524 +	89 -	1532 +	16	LT
738	TOTAL					

25100630 EROSION CONTROL BLANKET

SQ YD	LOCATION					
444		1524 +	29.22 -	1527 +	55.59	LT & RT
411		1529 +	53.31 -	1532 +	16.29	LT & RT
832	TOTAL					

28000400 PERIMETER EROSION BARRIER

FOOT	LOCATION					
435		1524 +	29.22 -	1527 +	1.7	LT & RT
471		1528 +	50.93 -	1532 +	16.29	LT & RT
906	TOTAL					

44000007 BITUMINOUS CONCRETE SURFACE REMOVAL 2"

SQ YD	LOCATION				
71		1527 +	35.59 -	1527 +	55.59
71		1528 +	50.93 -	1528 +	70.93
142	TOTAL				

48101200 AGGREGATE SHOULDERS, TYPE B

TON	LOCATION				
100		1524 +	29.22 -	1527 +	55.59
100		1528 +	50.93 -	1532 +	16.29
200	TOTAL				

48202600 BITUMINOUS SHOULDERS SUPERPAVE 2"

SQ YD	LOCATION				
12.0		1527 +	35.59 -	1527 +	55.59
12.0		1528 +	50.93 -	1528 +	70.93
24.0	TOTAL				

63100087 TRAFFIC BARRIER TERMINAL, TYPE 6A

EACH	LOCATION					
1		1527 +	14.22	-	1527 +	48.12 RT
1		1527 +	28.74	-	1527 +	62.64 LT
1		1528 +	43.74	-	1528 +	77.64 RT
1		1528 +	58.19	-	1528 +	92.09 LT
4	TOTAL					

63100169 TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (FLARED)

EACH	LOCATION					
1		1524 +	64.22	-	1524 +	76.72 RT
1	TOTAL					

63100167 TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)

EACH	LOCATION					
1		1525 +	28.74	-	1525 +	41.24 LT
1		1530	65.14	-	1530	77.64 RT
1		1531 +	54.59	-	1531 +	67.09 LT
3	TOTAL					

63200310 GUARDRAIL REMOVAL

FOOT	LOCATION					
39		1524 +	85.71	-	1525 +	24.44 RT
50		1525 +	32.86	-	1525 +	84.4 LT
34		1527 +	14.37	-	1527 +	48.12 RT
34		1527 +	48.12	-	1527 +	62.49 LT
34		1528 +	43.8	-	1528 +	77.64 RT
34		1528 +	58.19	-	1528 +	92.09 LT
50		1530 +	21.74	-	1530 +	74.29 RT
50		1531 +	16.19	-	1531 +	69.34 LT
325	TOTAL					

63301210 REMOVE AND RE-ERECT STEEL PLATE BEAM GUARDRAIL, TYPE A

FOOT	LOCATION					
237.5		1524	76.72	-	1527	14.22 RT
187.5		1525	41.24	-	1527	28.74 LT
187.5		1528 +	77.64	-	1530 +	65.14 RT
262.5		1528 +	92.09	-	1531 +	54.59 LT
875	TOTAL					

63500105 DELINEATORS

EACH	LOCATION			
1		1524 +	64.22	RT
1		1525 +	28.74	LT
1		1530 +	65.14	RT
1		1531 +	54.59	LT
4	TOTAL			

70400100 TEMPORARY CONCRETE BARRIER

FOOT	LOCATION				
516.0		1525 +	20 -	1530 +	34.79
516	TOTAL				

70400200 RELOCATE TEMPORARY CONCRETE BARRIER

FOOT	LOCATION				
492.0		1525 +	69.56 -	1530 +	61.14
492	TOTAL				

78001110 PAINT PAVEMENT MARKING LINE 4"

FOOT	LOCATION						
3148		1524 +	29.22	-	1532 +	16.29	WHITE EDGELINES - 2 COATS
3148		1524 +	29.22	-	1532 +	16.29	DBL YELLOW - 2 COATS
6296	TOTAL						

78100100 RAISED REFLECTIVE PAVEMENT MARKER

EACH	LOCATION		
1		1527 +	45
1		1528 +	60
2	TOTAL		

78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

EACH	LOCATION		
1		1527 +	45
1		1528 +	60
2	TOTAL		

X2500200 TEMPORARY EROSION CONTROL

POUND	LOCATION					
75		1524 +	29.22 -	1527 +	55.59	LT & RT
75		1528 +	50.93 -	1532 +	16.29	LT & RT
150	TOTAL					

X4066414 BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX C, N50

TON	LOCATION				
10		1527 +	35.59 -	1527 +	55.59
10		1528 +	50.93 -	1528 +	70.93
20	TOTAL				

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

SCHEDULE OF QUANTITIES

PLOT DATE = Fri Sep 02 11:37:51 2005
FILE NAME = c:\projects\s200105\s80105cvr.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = mesgilj