

URBAN

90% FED
10% STATE
Y031-1F

CONTRACT NO. 64831

F.A. R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
517	(1-3)TS-1	BOONE	12	2
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

Summary of Quantities for US 20 with Lawrenceville Rd				
PAY CODE	ITEM	UNIT	TOTAL	
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	115	
60100070	SHOULDER REMOVAL AND REPLACEMENT	FOOT	140	
60618300	CONCRETE MEDIAN SURFACE , 4 INCH	SQ FT	115	
67100100	MOBILIZATION	L SUM	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	
* 72000100	SIGN PANEL TYPE I	SQ FT	51	
* 72000200	SIGN PANEL TYPE II	SQ FT	30	
72400310	REMOVE EXISTING SIGN PANEL, TYPE I	SQ FT	21	
80501000	SERVICE INSTALLATION, (SPECIAL)	EACH	1	
81400400	CONCRETE HANDHOLE	EACH	10	
81400600	CONCRETE DOUBLE HANDHOLE	EACH	1	
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP TYPE USE) 1/C NO. 10	FOOT	1558	
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	4	
82500605	LIGHTING CONTROLLER PHOTOCELL RELAY	EACH	1	
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1	
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 5C	FOOT	2435	
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 7C	FOOT	890	
87301515	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 3 PR	FOOT	2843	
87301815	ELECTRIC CABLE IN CONDUIT, SERVICE, NO 6 3C	FOOT	33	
87502490	TRAFFIC SIGNAL POST GALVANIZED, 15 FT	EACH	4	
87702870	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 28 FT	EACH	1	
87702910	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 36 FT	EACH	1	
87703000	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 55 FT	EACH	2	
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	6	
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	3.5	
87800400	CONCRETE FOUNDATION, TYPE E, 30-INCH DIAMETER	FOOT	10	
87800415	CONCRETE FOUNDATION, TYPE E, 36-INCH DIAMETER	FOOT	41	
88200400	TRAFFIC SIGNAL BACKPLATE, FORMED PLASTIC	EACH	10	
88500100	INDUCTIVE LOOP DETECTOR	EACH	10	
88600100	DETECTOR LOOP TYPE I	FOOT	1099	
X0323153	ELECTRIC CABLE IN CONDUIT, GROUND, NO. 6 1 C (GREEN)	FOOT	695	
X0324885	CONDUIT INSTALLED, 1", NON-METALLIC	FOOT	52	
X0324886	CONDUIT INSTALLED, 1 1/4", NON-METALLIC	FOOT	740	
X0324887	CONDUIT INSTALLED, 2 1/2", NON-METALLIC	FOOT	189	
X0324888	CONDUIT INSTALLED, 4", NON-METALLIC	FOOT	349	
* X7800510	POLYUREA PAVEMENT MARKING, SPECIAL, LINE 4"	FOOT	4400	
* X7800540	POLYUREA PAVEMENT MARKING, SPECIAL, LINE 8"	FOOT	1157	
* X7800550	POLYUREA PAVEMENT MARKING, SPECIAL, LINE 12"	FOOT	527	
* X7800580	POLYUREA PAVEMENT MARKING, SPECIAL, LINE 24"	FOOT	227	
X8801300	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2	
X8801310	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	8	
X8801400	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	2	
X8801437	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3-SECTION, 1-5-SECTION, BRACKET MOUNTED	EACH	2	
* X7800500	POLYUREA PAVEMENT MARKING, SYMBOLS AND LETTERS, SPECIAL	SQ FT.	17.4	

* SPECIALTY ITEMS

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. HORIZ. DATE

DRAWN BY
CHECKED BY

PLOT DATE = Thu Sep 01 11:34:28 2005
FILE NAME = c:\prowork\12091405\c894985.dgn
PLOT SCALE = 200/866 = 1/4"
USER NAME = TUNA