

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
412	(50-8VB)I	LASALLE	31	3
FED. ROAD DIST. NO. - ILLINOIS				

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE:

SFTY-2A

CODE NO.	ITEM	UNIT	100% STATE TOTAL QUANTITY
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	134
40600990	TEMPORARY RAMP	SQ YD	168
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	540
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	144
44000700	APPROACH SLAB REMOVAL	SQ YD	408
44001430	BITUMINOUS SHOULDER REMOVAL	SQ YD	136
50102400	CONCRETE REMOVAL	CU YD	82
50200100	STRUCTURE EXCAVATION	CU YD	134
50301245	FORMED CONCRETE REPAIR (DEPTH EQUAL TO OR LESS THAN 5")	SQ FT	26
50300255	CONCRETE SUPERSTRUCTURE	CU YD	82
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	14772
51205200	TEMPORARY SHEET PILING	SQ FT	648
60100925	PIPE DRAINS 8"	FOOT	180
63300575	REMOVE AND RE-ERECT RAIL ELEMENT OF EXISTING GUARDRAIL	FOOT	200
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6
67100100	MOBILIZATION	L SUM	1

JULY 1, 2005
C:\PROJECTS\GMA\ING6\CM3\B\DETAILS.DGN

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 F.A.I. 412 OVER BNSF RAILROAD
 SECTION (50-8VB)I
 LASALLE COUNTY
 STA. 758 + 10
 DATE 06/01/2005
 DRAWN BY RLW