

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
412	150-8VB1	LASALLE	31	4
FED. ROAD DIST. NO. ILLINOIS				

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE: SFTY-2A

CODE NO.	ITEM	UNIT	100% STATE TOTAL QUANTITY
70101605	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402 (SPECIAL)	EACH	2
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	10320
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3406
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1200
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1100
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	10320
* 78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	1420
78300100	PAVEMENT MARKING REMOVAL	SQ FT	3406
XX005128	STRIP SEAL EXPANSION JOINT ASSEMBLY	FOOT	168
X0300136	BRIDGE APPROACH SHOULDER REMOVAL	SQ YD	132
X0322194	POLYMER MODIFIED PORTLAND CEMENT MORTAR	SQ FT	15
Z0002600	BAR SPLICERS	EACH	532
Z0015700	DECK DRAIN REPLACEMENT	EACH	4
● Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2
● Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1

●SFTY-3N * SPECIALTY ITEMS

JULY 1, 2005 C:\PROJECTS\DMA\ING6\CM318\DETAILS.DGN

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
 F.A.I. 412 OVER BNSF RAILROAD
 SECTION (50-8VB1)
 LASALLE COUNTY
 STA. 758+10

DATE 06/01/2005

DRAWN BY R.L.W