

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
412	(50-8VB)I	LASALLE	31	6
FED. ROAD DIST. NO. ILLINOIS				

BRIDGE APPROACH PAVEMENT (SPECIAL)			
STAGE I			
NORTHBOUND	NORTH ABUT	67.5	SQ YD
STRUCTURE	SOUTH ABUT	67.5	SQ YD
SOUTHBOUND	NORTH ABUT	67.5	SQ YD
STRUCTURE	SOUTH ABUT	67.5	SQ YD
SUBTOTAL		270	SQ YD
STAGE II			
NORTHBOUND	NORTH ABUT	67.5	SQ YD
STRUCTURE	SOUTH ABUT	67.5	SQ YD
SOUTHBOUND	NORTH ABUT	67.5	SQ YD
STRUCTURE	SOUTH ABUT	67.5	SQ YD
SUBTOTAL		270	SQ YD
TOTAL		540	SQ YD

CONCRETE SUPERSTRUCTURE			
STAGE I			
NORTHBOUND	NORTH ABUT	10.25	CU YD
STRUCTURE	SOUTH ABUT	10.25	CU YD
SOUTHBOUND	NORTH ABUT	10.25	CU YD
STRUCTURE	SOUTH ABUT	10.25	CU YD
SUBTOTAL		41	CU YD
STAGE II			
NORTHBOUND	NORTH ABUT	10.25	CU YD
STRUCTURE	SOUTH ABUT	10.25	CU YD
SOUTHBOUND	NORTH ABUT	10.25	CU YD
STRUCTURE	SOUTH ABUT	10.25	CU YD
SUBTOTAL		41	CU YD
TOTAL		82	CU YD

BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)			
STAGE I			
NORTHBOUND	NORTH ABUT	18	SQ YD
STRUCTURE	SOUTH ABUT	18	SQ YD
SOUTHBOUND	NORTH ABUT	18	SQ YD
STRUCTURE	SOUTH ABUT	18	SQ YD
SUBTOTAL		72	SQ YD
STAGE II			
NORTHBOUND	NORTH ABUT	18	SQ YD
STRUCTURE	SOUTH ABUT	18	SQ YD
SOUTHBOUND	NORTH ABUT	18	SQ YD
STRUCTURE	SOUTH ABUT	18	SQ YD
SUBTOTAL		72	SQ YD
TOTAL		144	SQ YD

STRIP SEAL EXPANSION JOINT ASSEMBLY			
STAGE I			
NORTHBOUND	NORTH ABUT	21	FEET
STRUCTURE	SOUTH ABUT	21	FEET
SOUTHBOUND	NORTH ABUT	21	FEET
STRUCTURE	SOUTH ABUT	21	FEET
SUBTOTAL		84	FEET
STAGE II			
NORTHBOUND	NORTH ABUT	21	FEET
STRUCTURE	SOUTH ABUT	21	FEET
SOUTHBOUND	NORTH ABUT	21	FEET
STRUCTURE	SOUTH ABUT	21	FEET
SUBTOTAL		84	FEET
TOTAL		168	FEET

JULY 1, 2005
C:\PROJECTS\CMA\106\CM318\DETAILS.DGN

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULES
F.A.I. 412 OVER BNSF RAILROAD
SECTION (50-8VB)I
LASALLE COUNTY
STA. 758 + 10
DATE 06/01/2005
DRAWN BY RLW