

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
412	150-8VB)I	LASALLE	31	7
FED. ROAD DIST. NO.		ILLINOIS		

TEMPORARY PAVEMENT MARKING LINE 4"		
STAGE I		
NORTHBOUND STRUCTURE	2840	FEET
SOUTHBOUND STRUCTURE	2840	FEET
<b>SUBTOTAL</b>	<b>5680</b>	<b>FEET</b>
STAGE II		
NORTHBOUND STRUCTURE	2320	FEET
SOUTHBOUND STRUCTURE	2320	FEET
<b>SUBTOTAL</b>	<b>4640</b>	<b>FEET</b>
<b>TOTAL</b>	<b>10320</b>	<b>FEET</b>

TEMPORARY CONCRETE BARRIER		
STAGE I		
NORTHBOUND STRUCTURE	600	FEET
SOUTHBOUND STRUCTURE	600	FEET
<b>SUBTOTAL</b>	<b>1200</b>	<b>FEET</b>

WORK ZONE PAVEMENT MARKING REMOVAL		
STAGE I		
NORTHBOUND STRUCTURE	937	SQ FT
SOUTHBOUND STRUCTURE	937	SQ FT
<b>SUBTOTAL</b>	<b>1874</b>	<b>SQ FT</b>
STAGE II		
NORTHBOUND STRUCTURE	766	SQ FT
SOUTHBOUND STRUCTURE	766	SQ FT
<b>SUBTOTAL</b>	<b>1531</b>	<b>SQ FT</b>
<b>TOTAL</b>	<b>3406</b>	<b>SQ FT</b>

RELOCATE TEMPORARY CONCRETE BARRIER		
STAGE II		
NORTHBOUND STRUCTURE	550	FEET
SOUTHBOUND STRUCTURE	550	FEET
<b>SUBTOTAL</b>	<b>1100</b>	<b>FEET</b>

EPOXY PAVEMENT MARKING LINE 4"		
STAGE II		
NORTHBOUND STRUCTURE	5160	FEET
SOUTHBOUND STRUCTURE	5160	FEET
<b>SUBTOTAL</b>	<b>10320</b>	<b>FEET</b>

PAVEMENT MARKING REMOVAL		
STAGE I		
NORTHBOUND STRUCTURE	937	SQ FT
SOUTHBOUND STRUCTURE	937	SQ FT
<b>SUBTOTAL</b>	<b>1874</b>	<b>SQ FT</b>
STAGE II		
NORTHBOUND STRUCTURE	766	SQ FT
SOUTHBOUND STRUCTURE	766	SQ FT
<b>SUBTOTAL</b>	<b>1531</b>	<b>SQ FT</b>
<b>TOTAL</b>	<b>3406</b>	<b>SQ FT</b>

EPOXY PAVEMENT MARKING LINE 6"		
STAGE II		
NORTHBOUND STRUCTURE	710	FEET
SOUTHBOUND STRUCTURE	710	FEET
<b>SUBTOTAL</b>	<b>1420</b>	<b>FEET</b>

JULY 1, 2005  
C:\PROJECTS\CM11\06\CM318\DETAILS.DGN

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULES**  
F.A.I. 412 OVER BNSF RAILROAD  
SECTION (50-8VB)I  
LASALLE COUNTY  
STA. 758 + 10

DATE 06/01/2005

DRAWN BY RLW