

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	*	McLEAN	5	2
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

*D3 TREE PLANTING 2006-1

GENERAL NOTES

(Revised January 1, 2002)

SEEDING SHALL NOT BE PERMITTED AT ANY TIME WHEN THE GROUND IS FROZEN, WET, OR IN AN UNTILLABLE CONDITION. LOCATIONS TO BE SEEDED WILL BE DETERMINED BY THE ENGINEER.

ABANDONED UNDERGROUND UTILITIES THAT CONFLICT WITH CONSTRUCTION SHALL BE DISPOSED OF OUTSIDE THE LIMITS OF THE RIGHT OF WAY ACCORDING TO ARTICLE 202.03 OF THE STANDARD SPECIFICATIONS AND AS DIRECTED BY THE ENGINEER. THIS WORK WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN THE COST OF MOBILIZATION

ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUBNUMBER LISTED ON THE INDEX OF SHEETS OR THE COPY OF THE STANDARD INCLUDED IN THESE PLANS.

THE CONTRACTOR'S ATTENTION IS DIRECTED TO THE PRESENCE OF DEPARTMENT-OWNED UNDERGROUND ELECTRICAL CABLE WITHIN THE LIMITS OF THE PROPOSED IMPROVEMENT. THE CONTRACTOR SHALL REQUEST THE ILLINOIS DEPARTMENT OF TRANSPORTATION TO LOCATE THE UNDERGROUND FACILITIES, PROVIDING A MINIMUM OF 72 HOURS NOTICE. THE DEPARTMENT IS NOT A MEMBER OF THE JOINT UTILITY LOCATING INFORMATION FOR EXCAVATORS (JULIE) SYSTEM.

ALL DAMAGE TO DEPARTMENT OWNED UNDERGROUND FACILITIES, CAUSED BY THE CONTRACTOR SHALL BE REPAIRED TO THE SATISFACTION OF THE DEPARTMENT AT THE CONTRACTOR'S EXPENSE. THIS SHALL INCLUDE ALL TEMPORARY REPAIRS REQUIRED TO KEEP THE FACILITY OPERATIONAL WHILE MATERIAL IS BEING OBTAINED TO MAKE PERMANENT REPAIRS. SPLICING OF ELECTRIC CABLE SHALL NOT BE ALLOWED. ELECTRIC CABLE SHALL BE REPLACED FROM POLE TO POLE OR CONTROLLER.

MEMBERS OF JULIE KNOWN TO BE WITHIN THE LIMITS OF THE IMPROVEMENT ARE:

- AMEREN IP
- CORN BELT ENERGY
- VERIZON
- NICOR GAS
- INSIGHT COMMUNICATIONS
- TOWN OF NORMAL
- CITY OF BLOOMOMGTON
- SPRINT COMMUNICATIONS
- MCI
- LEVEL 3 COMMUNICATIONS

NON-MEMBERS OF JULIE KNOWN TO BE WITHIN THE LIMITS OF THE IMPROVEMENT ARE:

STATE OF ILLINOIS - IDOT

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
DISTRICT THREE

REVIEWED BY: Steve B. Andrews
ACTING DISTRICT STUDIES & PLANS ENGINEER

DATE: SEPTEMBER 6, 2005

EXAMINED BY: Hubert J. ...
DISTRICT CONSTRUCTION ENGINEER

Kenneth R. Lewis
DISTRICT MATERIALS ENGINEER
James A. ...
DISTRICT OPERATIONS ENGINEER

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	URBAN
			TOTAL QUANTITY
A2000116	TREE,ACER X FREEMANII AUTUMN BLAZE (AUTUMN BLAZE(AUTUMN BLAZE FREEMAN MAPLE),2" CALIPER, BALLED AND BURLAPPED	EACH	30
A2005016	TREE,GYMNOCCLADUS DIOICUS (KENTUCKY COFFEETREE) 2" CALIPER, BALLED AND BURLAPPED	EACH	32
A2002916	TREE,CELTIS OCCIDENTALIS (COMMON HACKBERRY) 2" CALIPER,BALLED AND BURLAPPED	EACH	30
C2C01524	SHRUB, CORNUS RACEMOSA (GRAY DOGWOOD) 2' HEIGHT, CONTAINER	EACH	200
D2001760	EVERGREEN, PICEA ABIES (NORWAY SPRUCE) 5' HEIGHT,BALLED AND BURLAPPED	EACH	55
67100100	MOBILIZATION	L.SUM	1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
GENERAL NOTES & SUMMARY OF QUANTITIES
SCALE: VERT. _____
DATE _____ HORIZ. _____
DRAWN BY _____
CHECKED BY _____