

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
687	*	McDonough / Fulton	58	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* D4 CULV EXT/ REPAIR 2006				

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO.	ITEM	UNITS	TOTAL QUANTITY	LOCATION 1 Y007 Mc Donough Co.	LOCATION 1 Y007 Fulton Co.	LOCATION 2 Y007 Fulton Co.	LOCATION 3 Y007 Fulton Co.
20100500	TREE REMOVAL, ACRES	ACRE	0.79	0.21		0.16	0.42
20101700	SUPPLEMENTAL WATERING	UNIT	15	5		5	5
20200100	EARTH EXCAVATION	CU YD	3,353	451	41	777	2,084
20400800	FURNISHED EXCAVATION	CU YD	1,952	374		248	1,330
21101615	TOPSOIL FURNISH & PLACE, 4"	SQ YD	6,636	1,405	121	1,855	3,255
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	153	34	1.00	45	73
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	153	34	1.00	45	73
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	153	34	1.00	45	73
* 25001700	SEEDING, CLASS 3 (MODIFIED)	ACRE	1.7	0.38	0.01	0.50	0.81
25100115	MULCH, METHOD 2	ACRE	1.7	0.38	0.01	0.50	0.81
25101005	HEAVY DUTY EXCELSIOR BLANKET	SQ YD	5,297	888	120	1,760	2,529
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	510	114	3	150	243
28000300	TEMPORARY DITCH CHECKS	EACH	36	8		10	18
28000400	PERIMETER EROSION BARRIER	FOOT	392	206		186	
28100107	STONE RIPRAP, CLAS A4	SQ YD	98	14		30	54

* SPECIALTY ITEMS

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO.	ITEM	UNITS	TOTAL QUANTITY	LOCATION 1 Y007 Mc Donough Co.	LOCATION 1 Y007 Fulton Co.	LOCATION 2 Y007 Fulton Co.	LOCATION 3 Y007 Fulton Co.
28100125	STONE RIPRAP, CLAS B3	SQ YD	1328	245		410	673
28200200	FILTER FABRIC	SQ YD	98	14		30	54
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	676	206	41	187	242
50102400	CONCRETE REMOVAL	CU YD	3			1	2
50800105	REINFORCEMENT BARS	POUND	136	24		70	42
54002020	EXPANSION BOLTS 3/4 INCH	EACH	30	10		10	10
54201291	PIPE CULVERT, TYPE 2 RCCP 36"	FOOT	57	20		11	26
54202971	PIPE CULVERT, TYPE 4 RCCP 36"	FOOT	70			25	45
54213681	PRECAST REINF. CONC. FLARED END SECTIONS 36"	EACH	5	1		2	2
54248510	CONCRETE COLLAR	CU YD	5.3	1.8		1.4	2.1
60221100	MANHOLES, TYPE A, 5'- DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	1		1	1
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	1,437.5	468.75	56.25	462.5	450
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	3		1	1	1
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	EACH	8	2	1	3	2