

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
687	*	McDonough / Fulton	58	9
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

\* D4 CULV EXT/REPAIR 2006

# SCHEDULE OF QUANTITIES

CODE NO.	50102400	50800105	54002020	54201291	54202971	54213681	54248510	60221100
	CONCRETE REMOVAL	REINFORCEMENT BARS	EXPANSION BOLTS 3/4 INCH	PIPE CULVERT TYPE 2 RCCP 36"	PIPE CULVERT TYPE 4 RCCP 36"	PRECAST REINF. CONC. FLARED END SECTION 36"	CONCRETE COLLAR	MANHOLES TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID
	CU YD	LBS	EACH	FOOT	FOOT	EACH	CU YD	EACH
LOCATION 1								
Lt. Sta. 160+35		24	10	20		1	1.8	1
LOCATION 2								
Lt. Sta. 352+70		25	10	11		1	0.5	
Rt. Sta. 352+70	1	45			25	1	0.9	1
LOCATION 3								
Lt. Sta. 403+36		42	10	26		1	2.1	
Rt. Sta. 403+36	2				45	1		1
<b>TOTAL =</b>	<b>3</b>	<b>136</b>	<b>30</b>	<b>57</b>	<b>70</b>	<b>5</b>	<b>5.3</b>	<b>3</b>

CODE NO.66600105

FURNISHING AND ERECTING RIGHT OF WAY MARKERS	
LOCATION 1	UNIT EACH
Sta.158+75, 40' Lt	1
Sta.159+75, 110' Lt	1
Sta. 160+25, 110' Lt	1
Sta. 161+00, 40' Lt	1
LOCATION 2	
Sta. 351+75, 75' Lt	1
Sta. 352+25, 110' Lt	1
Sta. 353+00, 110' Lt	1
Sta. 353+25, 75' Lt	1
Sta. 351+50, 75' Rt	1
Sta. 352+50, 130' Rt	1
Sta. 353+00, 130' Rt	1
Sta. 353+68.72, 75' Rt	1
LOCATION 3	
Sta. 401+30, 40' Lt	1
Sta.403+00, 130' Lt	1
Sta. 403+50, 130' Lt	1
Sta. 403+75, 93' Lt	1
Sta. 402+90, 78' Rt	1
Sta. 403+50, 150' Rt	1
Sta. 403+75, 105' Rt	1
Sta. 404+25, 83' Rt	1
<b>TOTAL = 20</b>	

CODE NO.63100167

TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	
LOCATION 1	UNIT EACH
Lt. Sta. 157+62.31 to Sta. 158+12.31	1
Lt. Sta. 161+37.31 to Sta. 161+87.31	1
Rt. Sta. 158+50 to Sta. 159+00	1
LOCATION 2	
Lt. Sta. 351+12.5 to Sta. 351+62.5	1
Rt. Sta. 350+00 to Sta. 350+50	1
Rt. Sta. 353+50 to Sta. 354+00	1
LOCATION 3	
Lt. Sta. 401+62.75 to Sta. 402+12.75	1
Rt. Sta. 401+00 to Sta. 401+50	1
<b>TOTAL = 8</b>	

CODE NO.67000400

ENGINEER'S FIELD OFFICE, TYPE A	
LOCATION	UNIT CAL MO
JOBSITE	3
<b>TOTAL = 3</b>	

CODE NO.67100100

MOBILIZATION	
LOCATION	UNIT L SUM
JOBSITE	1
<b>TOTAL = 1</b>	

CODE NO.63100169

TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	
LOCATION 3	UNIT EACH
Rt. Sta. 404+00 to Sta. 404+50	1
<b>TOTAL = 1</b>	

CODE NO.66502300

WOVEN WIRE FENCE REMOVAL	
LOCATION 1	UNIT FOOT
Sta.158+50 to Sta. 161+00	250
LOCATION 2	
Lt. Sta. 351+75 to Sta. 353+25	150
Rt. Sta. 351+50 to Sta. 353+75	225
LOCATION 3	
Lt Sta. 401+30 to Sta. 403+75	252
Lt. Sta. 402+11 to Sta. 402+22	13
Rt. Sta. 402+90 to Sta. 404+25	135
<b>TOTAL = 1,025</b>	

CODE NO.78200410

GUARDRAIL MARKER TYPE A	
LOCATION 1	UNIT EACH
Lt. Sta. 158+12.31 to Sta. 161+37.31	4
Rt. Sta. 159+00 to Sta. 160+95	3
LOCATION 2	
Lt. Sta. 351+62.5 to Sta. 353+21.7	2
Rt. Sta. 350+50 to Sta. 353+50	4
LOCATION 3	
Lt. Sta. 402+12.75 to Sta. 404+08	3
Rt. Sta. 401+50 to Sta. 404+00	3
<b>TOTAL = 19</b>	

CODE NO.70100450

TRAFFIC CONTROL AND PROTECTION STANDARD 701201	
LOCATION 1	UNIT L.SUM
Sta.157+00 to Sta. 162+50	0.2
LOCATION 2	
Sta. 349+50 to Sta. 353+50	0.4
LOCATION 3	
Sta. 400+50 to Sta. 405+00	0.4
<b>TOTAL = 1.0</b>	