

SCHEDULE OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	*	VERMILTON	13	5

*92(11,12,12-1)RS-1,1

PREF PL PM TAPE TB LINE 4

<u>LOCATION</u>	<u>FOOT</u>
LT. STA. 11+00 - 15+00	400

LOCATION	EARTH EXCAVATION CU YD	EARTH EXC ADJ FOR SHRINKAGE	EMBANKMENT CU YD	BALANCE (-) FILL CU YD (2)
STA. 11+00 TO 15+00	3.0	2.3	22.0	-19.75
TOTAL	5.0		25.0	20.0

NOTES:
 1- NO SHRINKAGE FACTOR APPLIED TO THE EMBANKMENT QUANTITY
 2- A 25% EXPANSION FACTOR WAS USED IN COMPUTING BORROW QUANTITY

5 CUYDS EARTH EXCAVATION
 25 CUYDS FURNISHED EXCAVATION

BITUMINOUS SHOULDER SUPERPAVE 3 1/2"

<u>LOCATION</u>	<u>SQ. YD.</u>
LT. 11+39.66 - LT. 14+63.79	197.0

ITEM	QUANTITY	UNIT
SEEDING CLASS 2	0.1	ACRE
SEEDING CLASS 7	0.1	ACRE
NITROGEN FERTILIZER NUTRIENT	9.0	POUND
PHOSPHOROUS FERTILIZER NUTRIENT	9.0	POUND
POTASSIUM FERTILIZER NUTRIENT	9.0	POUND
MULCH METHOD 2	0.1	ACRE

SEEDING, FERTILIZER, AND MULCH METHOD QUANTITIES WERE CALCULATED FROM LOCATIONS OFF OF THE CROSS SECTIONS.

BITUMINOUS SHOULDER REMOVAL

<u>LOCATION</u>	<u>SQ. YD.</u>
LT. 11+39.66 - LT. 14+63.79	197.0

AGGREGATE SHOULDERS, TYPE A

<u>LOCATION</u>	<u>TON</u>
LT. 11+39.66 - LT. 14+63.79	15.0