

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	81B-1	MORGAN	114	4
STA.		TO STA.		
CONTRACT NO. 72528				

CODED NO	DESCRIPTION	UNIT	QUANTITY	CONSTRUCTION CODE			
				LOCATION 1 80% FEDERAL 20% STATE ROADWAY 1000-2A	LOCATION 2 80% FEDERAL 20% STATE BOX CULVERT X028-2A	LOCATION 3 80% FEDERAL 20% STATE ROADWAY 1000-2A	LOCATION 4 80% FEDERAL 20% STATE BRIDGE X071-2A
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	8858	2368	2219	2072	2199
* 76001100	PAINT PAVEMENT MARKING - LINE 5"	FOOT	6728	1800	1685	1573	1670
70400100	TEMPORARY CONCRETE BARRIER	FOOT	425				425
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	425				425
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	39	10	10	9	10
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	28	10	10		8
* 78200520	BARRIER WALL MARKERS, TYPE B	EACH	2				2
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	12	4	4		4
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	39	10	10	9	10
X0321473	PIPE ELBOW, 15"	EACH	1			1	
X3550500	BITUMINOUS BASE COURSE SUPERPAVE 8"	SQ YD	757				757
X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	TON	700	179	167	172	182
X4066614	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL 19.0, N50	TON	825	428	112	104	181
X4409905	BITUMINOUS REMOVAL (MISCELLANEOUS)	SQ YD	51			51	
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1				1
X6330103	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL, TANGENT	EACH	4				4
XX004350	TRANSVERSE DRAINS COMPLETE	EACH	6	2	2	2	
Z0000990	AGGREGATE FOR TEMPORARY ACCESS	TON	66			66	
Z0002600	BAR SPLICERS	EACH	541				541
Δ Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2				2
Δ Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2				2
Z0076600	TRAINERS	HOUR	0				
X0323900	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	905				905
* Z0054517	ROCKFILL FOUNDATION	TON	775	225	325	225	
Z0075310	TIE BARS 3/4	EACH	170	56	57	57	
X7015000	CHANGEABLE MESSAGE SIGN	CAL MA	10	2.5	2.5	2.5	2.5

⊙ 4080
Δ SFTY-3N * SPECIALTY ITEMS

REVISIONS	
NAME	DATE
TMJ	08-03-05

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 FAP ROUTE 310 (US 67/IL 267)
 SECTION 81B-1
 MORGAN COUNTY
 SCALE: VERT. _____
 DATE _____
 DRAWN BY BANDY
 CHECKED BY STEUART

Rev.