

**SUMMARY OF QUANTITIES**

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	SN 086-7500	
				SCOTT COUNTY STP RURAL STATE FUNDS 80% FEDERAL / 20% STATE TOTAL QUANTITIES CONSTRUCTION TYPE CODE X02B-2A	SFTY-3N
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	16	16	
20200100	EARTH EXCAVATION	CU YD	300	300	
20400800	FURNISHED EXCAVATION	CU YD	990	990	
25000200	SEEDING, CLASS 2	ACRE	0.50	0.50	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	35	35	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	35	35	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	35	35	
25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.8	0.8	
25100105	MULCH, METHOD 1	ACRE	0.50	0.50	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	200	200	
28001000	AGGREGATE (EROSION CONTROL)	TON	9	9	
28000400	PERIMETER EROSION BARRIER	FOOT	646	646	
28100807	STONE DUMPED RIPRAP, CLASS A4	TON	146	146	
28200200	FILTER FABRIC	SQ YD	291	291	
35101400	AGGREGATE BASE COURSE, TYPE B	TON	88	88	
35800100	PREPARATION OF BASE	SQ YD	257	257	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1.8	1.8	
40600300	AGGREGATE (PRIME COAT)	TON	10	10	
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	358	358	
40600990	TEMPORARY RAMP	SQ YD	68	68	
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	6	6	
44000100	PAVEMENT REMOVAL	SQ YD	115	115	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	98	98	
48202000	BITUMINOUS SHOULDERS SUPERPAVE	TON	108	108	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1	
50200100	STRUCTURE EXCAVATION	CU YD	570	570	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	15540	15540	
54001000	BOX CULVERT END SECTIONS	EACH	2	2	
54003000	CONCRETE BOX CULVERTS	CU YD	75.0	75.0	
63200310	GUARDRAIL REMOVAL	FOOT	328	328	
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	8	8	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70101205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)	EACH	1	1	

**SUMMARY OF QUANTITIES**

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	SN 086-7500	
				SCOTT COUNTY STP RURAL STATE FUNDS 80% FEDERAL / 20% STATE TOTAL QUANTITIES CONSTRUCTION TYPE CODE X02B-2A	SFTY-3N
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	367	367	
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	2273	2273	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	999	999	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	425	425	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	375	375	
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	3100	3100	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	10	10	
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	436	436	
X0324118	GRANULAR CULVERT BACKFILL	CU YD	350	350	
X3550700	BITUMINOUS BASE COURSE SUPERPAVE 10"	SQ YD	221	221	
X3560140	BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 10 INCH	SQ YD	771	771	
X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	TON	188	188	
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	TON	109	109	
X7200201	WIDTH RESTRICTION SIGNING	L SUM	1	1	
Z0000990	AGGREGATE FOR TEMPORARY ACCESS	TON	58	58	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0002600	BAR SPLICERS	EACH	43	43	
* Z0054517	ROCK FILL - FOUNDATION	TON	150	150	

\*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
F.A.P. ROUTE 562 (IL 100)  
SCOTT COUNTY

SCALE: VERT. NONE  
HORIZ. NONE  
DATE 04/27/2005

DRAWN BY AJP  
CHECKED BY JDJ