

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
609	***	ST. CLAIR	46	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
*** SEC. 76-3BR				
CONTRACT NO. 76268				

TREE REMOVAL

ACRE	LOCATION
0.3	STA. 135+50 RT. TO STA. 139+00 RT.
0.3	TOTAL

EARTH EXCAVATION

CU YD	LOCATION
283	STA. 135+60 TO STA. 138+14.56
61	STA. 139+17.56 TO STA. 141+90
344	TOTAL

FURNISHED EXCAVATION

CU YD	LOCATION
1106	STA. 135+60 TO STA. 138+14.56
605	STA. 139+17.56 TO STA. 141+90
1711	TOTAL

SEEDING, CLASS 2

ACRE	LOCATION
0.3	STA. 135+60 LT. TO STA. 138+14 LT.
0.3	STA. 135+60 RT. TO STA. 138+14 RT.
0.2	STA. 139+17 LT. TO STA. 141+90 LT.
0.3	STA. 139+17 RT. TO STA. 141+90 RT.
1.1	TOTAL

NITROGEN FERTILIZER NUTRIENT

POUND	LOCATION
27	STA. 135+60 LT. TO STA. 138+14 LT.
27	STA. 135+60 RT. TO STA. 138+14 RT.
18	STA. 139+17 LT. TO STA. 141+90 LT.
27	STA. 139+17 RT. TO STA. 141+90 RT.
99	TOTAL

NITROGEN FERTILIZER NUTRIENT

POUND	LOCATION
27	STA. 135+60 LT. TO STA. 138+14 LT.
27	STA. 135+60 RT. TO STA. 138+14 RT.
18	STA. 139+17 LT. TO STA. 141+90 LT.
27	STA. 139+17 RT. TO STA. 141+90 RT.
99	TOTAL

NITROGEN FERTILIZER NUTRIENT

POUND	LOCATION
27	STA. 135+60 LT. TO STA. 138+14 LT.
27	STA. 135+60 RT. TO STA. 138+14 RT.
18	STA. 139+17 LT. TO STA. 141+90 LT.
27	STA. 139+17 RT. TO STA. 141+90 RT.
99	TOTAL

MULCH METHOD 1 (3 APPLICATIONS)

ACRE	LOCATION
0.9	STA. 135+60 LT. TO STA. 138+14 LT.
0.9	STA. 135+60 RT. TO STA. 138+14 RT.
0.6	STA. 139+17 LT. TO STA. 141+90 LT.
0.9	STA. 139+17 RT. TO STA. 141+90 RT.
3.3	TOTAL

MULCH METHOD 2

ACRE	LOCATION
0.3	STA. 135+60 LT. TO STA. 138+14 LT.
0.3	STA. 135+60 RT. TO STA. 138+14 RT.
0.2	STA. 139+17 LT. TO STA. 141+90 LT.
0.3	STA. 139+17 RT. TO STA. 141+90 RT.
1.1	TOTAL

TEMPORARY EROSION CONTROL SEEDING (3 APPLICATIONS)

ACRE	LOCATION
0.9	STA. 135+60 LT. TO STA. 138+14 LT.
0.9	STA. 135+60 RT. TO STA. 138+14 RT.
0.6	STA. 139+17 LT. TO STA. 141+90 LT.
0.9	STA. 139+17 RT. TO STA. 141+90 RT.
3.3	TOTAL

TEMPORARY DITCH CHECKS

EACH	LOCATION
1	STA. 137+25 LT.
1	STA. 138+00 LT.
2	TOTAL

PERIMETER EROSION BARRIER

FOOT	LOCATION
259	STA. 135+75, 65' RT. TO STA. 138+35, 68' RT.
131	STA. 138+35, 68' RT. TO STA. 138+35, 63' LT.
122	STA. 138+85, 68' RT. TO STA. 139+00, 51' LT.
267	STA. 138+85, 68' RT. TO STA. 141+50, 48' RT.
149	STA. 139+00, 51' LT. TO STA. 140+46, 40' LT.
74	STA. 140+76, 40' LT. TO STA. 141+50, 38' LT.
1002	TOTAL

INLET AND PIPE PROTECTION

EACH	LOCATION
1	STA. 136+42 LT.
1	TOTAL

STONE DUMPED RIPRAP, CLASS A4

SQ YD	LOCATION
63	STA. 135+75 RT.
63	TOTAL

FILTER FABRIC FOR USE WITH RIPRAP

SQ YD	LOCATION
63	STA. 135+75 RT.
63	TOTAL

AGGREGATE SURFACE COURSE, TYPE B

TON	LOCATION
62	STA. 136+65 LT, FIELD ENTRANCE
120	STA. 136+65 LT, FIELD ENTRANCE (TEMP. ACCESS)
80	STA. 140+61 LT, PRIVATE ENTRANCE (TEMP. ACCESS)
262	TOTAL

BITUMINOUS MATERIALS (PRIME COAT)

GALLON	LOCATION
59	STA. 135+60 TO STA. 137+79.39
64	STA. 139+51.73 TO STA. 141+90
123	TOTAL

AGGREGATE (PRIME COAT)

TON	LOCATION
2	STA. 135+60 TO STA. 137+79.39
2	STA. 139+51.73 TO STA. 141+90
4	TOTAL

BITUMINOUS SURFACE REMOVAL - BUTT JOINT

SQ YD	LOCATION
240	STA. 135+60 TO STA. 136+50
240	STA. 141+00 TO STA. 141+90
480	TOTAL

TEMPORARY RAMP

SQ YD	LOCATION
14	STA. 135+60
120	STA. 137+40 TO STA. 137+85.39
120	STA. 139+46.73 TO STA. 139+92
14	STA. 141+90
268	TOTAL

BRIDGE APPROACH PAVEMENT

SQ YD	LOCATION
122	STA. 137+85.39 TO STA. 138+15.39
122	STA. 139+16.73 TO STA. 139+46.73
244	TOTAL

BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)

SQ YD	LOCATION
25	STA. 137+79.39 TO STA. 137+85.39
25	STA. 139+46.73 TO STA. 139+51.73
50	TOTAL

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAP 609 (IL RTE. 163)
SECTION 76-3BR
ST. CLAIR COUNTY

SCALE: VERT. _____
HORIZ. _____
DATE: 6/13/03

DRAWN BY: SUTHEARD
DESIGNED BY: SUTHEARD
CHECKED BY: COLBROOK

GREENE & BRADFORD, INC.
OF SPRINGFIELD
CORPORATE HEADQUARTERS
1000 N. UNIVERSITY
SPRINGFIELD, ILLINOIS 62761
TEL: 217-223-1100 FAX: 217-223-1101
WWW.GREENEANDBRADFORD.COM

COMPUTER FILE NO.
SUM163BR
PROJECT 02076
6/30/05-MDS

PLAN SURVEYED BY DATE
PLOTTED BY DATE
CHECKED BY DATE
NOTE BOOK NO. _____
ADD FILE NAME

PROFILE SURVEYED BY DATE
PLOTTED BY DATE
CHECKED BY DATE
NOTE BOOK NO. _____
STRUCTURE NOTATIONS CHECKED

FILE NAME: _____
PLOT SCALE: _____
PLOT DATE: _____
PLOT TIME: _____
OPERATOR: _____