

# SUMMARY OF QUANTITIES

F&P NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
609	76-1BR-2	ST. CLAIR	13	3
STA.		TO STA.		
CONTRACT NO. 76662				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	QUANTITIES	BRIGDE X080-2A SN 082-0213
20400800	FURNISHED EXCAVATION	CU YD	50	50
25000210	SEEDING, CLASS 2A	ACRE	0.5	0.5
25100105	MULCH, METHOD 1	ACRE	0.5	0.5
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	100	100
40600300	BITUMINOUS MATERIAL (PRIME COAT)	TON	0.2	0.2
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	416	416
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	11	11
48101200	AGGREGATE SHOULDERS, TYPE B	TON	6	6
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1	1
50102400	CONCRETE REMOVAL	CU YD	18.7	18.7
<del>50104000</del>	<del>BRIDGE RAIL REMOVAL</del>	<del>FOOT</del>	<del>255</del>	<del>255</del>
50300225	CONCRETE STRUCTURES	CU YD	18.7	18.7
50300300	PROTECTIVE COAT	SQ YD	456	456
50300260	BRIDGE DECK GROOVING	SQ YD	405	405
50301245	FORMED CONCRETE REPAIR (DEPTH EQUAL TO OR LESS THAN 5")	SQ FT	8	8
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	4092	4092
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	7810	7810
50901005	STEEL BRIDGE RAIL, TYPE SM	FOOT	255	255
51500100	NAME PLATES	EACH	1	1
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4
63200310	GUARDRAIL REMOVAL	FOOT	125	125
63301210	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	25	25
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	1
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	619	619
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	18	18
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	500	500
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	7	7
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	16	16
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	6	6
X0320887	POLYMER CONCRETE	CU FT	2.3	2.3
X0322932	SILICONE JOINT SEALER, 1.5"	FOOT	67	67
X0324952	DETOUR SIGNING	L. SUM	1	1
X4066416	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N70	TON	20	20
X4066770	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	TON	20	20
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	456	456
X7015000	CHANGEABLE MESSAGE SIGN	CAL MD	0	0
20001900	ASBESTOS BEARING PAD REMOVAL	EACH	38	38

\*SPECIALTY ITEMS

Rev. 11-1-05