



**INTERCONNECT QUANTITIES**

- 4613 FOOT ELECTRIC CABLE IN CONDUIT, COMMUNICATION NO. 18, 3 PAIR
- 4613 FOOT REMOVE ELECTRIC CABLE FROM CONDUIT

**CONSTRUCTION NOTES**

1. REMOVE THE EXISTING INTERCONNECT CABLE, THE APPROXIMATE LENGTH IS 2,345 FEET FROM THE MCHENRY AVE. CONTROLLER TO THE DOLE AVE. CONTROLLER ALONG U.S. ROUTE 14. SEE SHEET NO. 12, 13 & 17 FOR DETAILS.
2. REMOVE THE EXISTING INTERCONNECT CABLE, THE APPROXIMATE LENGTH IS 2,268 FEET FROM THE MCHENRY AVE. CONTROLLER TO THE KEITH AVE. CONTROLLER ALONG U.S. ROUTE 14. SEE SHEET NO. 12, 13 & 17 FOR DETAILS.

ILLINOIS DEPARTMENT OF TRANSPORTATION	
INTERCONNECT SCHEMATIC	
(DOLE AVENUE TO KEITH AVENUE)	
U.S. ROUTE 14	
NAME	DATE
REVISIONS	
SCALE: NONE	DRAWN BY: E.F.
DATE:	DESIGNED BY: J.L.
	CHECKED BY: P.K.