

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	80% Federal 20% State		ACF		ROADWAY QUANTITY 1000	SN 098-6000 QUANTITY X271-2A	SN 098-6001 QUANTITY X171-2A	HIGHWAY LTG QUANTITY Y030-1E
				ACF	ACBHF	ACF					
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	8								
20200100	EARTH EXCAVATION	CU YD	2910								
20400800	FURNISHED EXCAVATION	CU YD	3088								
20700400	POROUS GRANULAR EMBANKMENT (SPECIAL)	CU YD	416.7				234.7	182			
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	17025								
25000210	SEEDING, CLASS 2A	ACRE	2.2								
25000310	SEEDING, CLASS 4	ACRE	1.6								
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	360								
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	360								
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	360								
25000750	MOWING	ACRE	2.2								
25000775	SELECTIVE MOWING STAKES	EACH	2								
25100115	MULCH, METHOD 2	ACRE	1.3								
25100630	EROSION CONTROL BLANKET	SQ YD	10939								
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	760								
28000400	PERIMETER EROSION BARRIER	FOOT	5725								
28000500	INLET AND PIPE PROTECTION	EACH	1								
28100105	STONE RIPRAP, CLASS A3	SQ YD	100								
28100107	STONE RIPRAP, CLASS A4	SQ YD	34								
28200200	FILTER FABRIC	SQ YD	1188.5				34	662.5	492		
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	330								
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	3817								
31200100	STABILIZED SUB-BASE 4"	SQ YD	5585								
35300300	PORTLAND CEMENT CONCRETE BASE COURSE 8"	SQ YD	2144								
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	2.4								
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	75								
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	10								
42000411	PORTLAND CEMENT CONCRETE PAVEMENT, 9/2" (JOINTED)	SQ YD	620								
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	542.8								
42001300	PROTECTIVE COAT	SQ YD	2753								
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	1401								
42100210	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 9/2"	SQ YD	189								
42100810	PAVEMENT REINFORCEMENT 9/2"	SQ YD	189								
42101080	WIDE FLANGE BEAM TERMINAL JOINT COMPLETE (SPECIAL)	EACH	2								
44000100	PAVEMENT REMOVAL	SQ YD	4033								
44000120	BITUMINOUS REMOVAL OVER PATCHES 5"	SQ YD	33								

△NON-PARTICIPATING

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	80% Federal 20% State		ACF		ROADWAY QUANTITY 1000	SN 098-6000 QUANTITY X271-2A	SN 098-6001 QUANTITY X171-2A	HIGHWAY LTG QUANTITY Y030-1E
				ACF	ACBHF	ACF					
44000400	GUTTER REMOVAL	FOOT	1383								
44002805	ISLAND REMOVAL	SQ FT	3631								
44003100	MEDIAN REMOVAL	SQ FT	1293								
44004250	PAVED SHOULDER REMOVAL	SQ YD	217								
44200120	PAVEMENT PATCHING TYPE II, 10"	SQ YD	27								
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	646								
48101200	AGGREGATE SHOULDERS, TYPE B	TON	994								
48202310	BITUMINOUS SHOULDERS SUPERPAVE, 5/2"	SQ YD	1284								
48300410	PORTLAND CEMENT CONCRETE SHOULDERS 9/2"	SQ YD	378								
50102400	CONCRETE REMOVAL	CU YD	144.8						72.8	72	
50104400	CONCRETE HEADWALL REMOVAL	EACH	2								
50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	2						1	1	
50200100	STRUCTURE EXCAVATION	CU YD	827.5						493.5	334	
50300225	CONCRETE STRUCTURES	CU YD	319.4						174	145.4	
50300255	CONCRETE SUPERSTRUCTURES	CU YD	588.7						318.5	270.2	
50300260	BRIDGE DECK GROOVING	SQ YD	1564						863	701	
50300300	PROTECTIVE COAT	SQ YD	1965						1086	879	
50300310	ELASTOMERIC BEARING ASSEMBLY, TYPE 1	EACH	49						28	21	
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1						0.55	0.45	
50500505	STUD SHEAR CONNECTORS	EACH	7353						4224	3129	
50500715	JACK AND REMOVE EXISTING BEARING	EACH	35						20	15	
50501110	STRUCTURAL STEEL REMOVAL	POUND	60185						32875	27310	
50501130	STRUCTURAL STEEL REPAIR	POUND	2100						1040	1060	
* 50600600	CLEANING AND PAINTING STEEL BRIDGE NO. 1	L SUM	1						1		
* 50600700	CLEANING AND PAINTING STEEL BRIDGE NO. 2	L SUM	1							1	
* 50606401	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 1	L SUM	1						1		
* 50606402	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 2	L SUM	1							1	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	149540						84650	64890	
51100100	SLOPEWALL 4"	SQ YD	138.2						72.2	66	
51100500	BITUMINOUS COATED AGGREGATE SLOPEWALL 6"	SQ YD	1154.5						662.5	492	
51201600	FURNISHING STEEL PILES HP12x53	FOOT	2190						1338	852	
51202700	DRIVING STEEL PILES	FOOT	2190						1338	852	

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 SCALE: VERT. _____
 HORIZ. _____
 DATE 08/25/2005
 DRAWN BY SWEET
 CHECKED BY ZELINSKAS