

SCHEDULE OF TREE REMOVAL		
20100110 TREE REMOVAL (6 TO 15 UNITS DIAMETER)		
STATION	LOCATION	UNITS
49+63.1	78' RT.	8

SCHEDULE OF EARTHWORK				
20200100 EARTH EXCAVATION				
20400800 FURNISHED EXCAVATION				
LOCATION	EARTH EXCAVATION	ADJUSTED EXCAVATION 25% SHRINK	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD
44+44.89 TO 46+36.03	260	195	201	-6
48+01.03 TO 50+15.95	298	224	672	-448
52+19.71 TO 55+00.00	464	348	2878	-2530
55+00.00 TO 70+95.00	247	185	806	-621
NORTH RAMP	820	615	422	+193
SOUTH RAMP	821	616	292	+324
<b>TOTAL</b>	<b>2910</b>	<b>2183</b>	<b>5271</b>	<b>-3088</b>

SCHEDULE OF EROSION CONTROL										
21101615 TOPSOIL FURNISH AND PLACE, 4"										
25000210 SEEDING, CLASS 2A										
25000310 SEEDING, CLASS 4										
25000400 NITROGEN FERTILIZER NUTRIENT										
25000500 PHOSPHORUS FERTILIZER NUTRIENT										
25000600 POTASSIUM FERTILIZER NUTRIENT										
25000750 MOWING										
25000775 SELECTIVE MOWING STAKES										
25100115 MULCH, METHOD 2										
25100630 EROSION CONTROL BLANKET										
LOCATION	F & P TOPSOIL 4"	SEEDING CLASS 2A	SEEDING CLASS 4	MULCH METHOD 2	EROSION CONTROL BLANKET	FERTILIZER NUTRIENTS			SELECT. MOWING STAKES	MOWING
	SQ YD	ACRE	ACRE	ACRE	SQ YD	NITROGEN LB	PHOS-PHORUS LB	POTASS-IUM LB	EACH	ACRE
44+45 to 46+89 RT	742		0.2		742	18	18	18		
44+45 to 47+09 LT	1404		0.3		1404	27	27	27		
47+24 to 50+70 RT	1498		0.3		1498	36	36	36		
47+45 to 50+90 LT	1935		0.4		1935	36	36	36		
51+57 to 53+12 RT	987		0.2		987	27	27	27		
53+12 to 302+50 RT	1757	0.4		0.3	491	36	36	36		0.4
51+70 to 53+20 LT	828		0.2		828	18	18	18		
53+20 to 202+00 LT	2472	0.6		0.4	446	54	54	54		0.6
302+00 to 70+95 RT	2692	0.6		0.3	1306	54	54	54		0.6
202+00 to 70+95 LT	2710	0.6		0.3	1302	54	54	54		0.6
53+20 LT									1	
53+12 RT									1	
<b>TOTAL</b>	<b>17,025</b>	<b>2.2</b>	<b>1.6</b>	<b>1.3</b>	<b>10,939</b>	<b>360</b>	<b>360</b>	<b>360</b>	<b>2</b>	<b>2.2</b>

SCHEDULE OF PAVEMENT REMOVAL							
44000100 PAVEMENT REMOVAL							
44000400 GUTTER REMOVAL							
44002805 ISLAND REMOVAL							
44003100 MEDIAN REMOVAL							
44004250 PAVED SHOULDER REMOVAL							
LOCATION		PAVEMENT REMOVAL	MEDIAN REMOVAL	GUTTER REMOVAL	ISLAND REMOVAL	PAVED SHOULDER REMOVAL	DESCRIPTION
STATION TO STATION	SIDE	SQ YD	SO FT	FT	SQ FT	SQ YD	
44+94.88	46+36.03	377					
48+01.03	50+15.95	574					
52+19.74	55+00.00	1174					
55+00.00	55+52.00	24					
55+52.00	60+32.00	124	1293				
60+32.00	61+32.00	39					
NORTH RAMP		797			1000		
SOUTH RAMP		924			2631		
44+94.8	45+61.1	LT					43
48+09.4	50+23.7	LT					52
52+25.7	53+11.5	LT					17
44+94.8	45+36.8	RT					28
47+90.0	50+09.9	RT					50
52+11.7	53+12.6	RT					27
45+61.1	46+47.2	LT		86.1			
45+36.8	46+28.0	RT		91.2			
48+09.2	50+23.9	LT		214.7			
47+90.1	50+10.0	RT		219.9			
52+25.5	53+11.5	LT		86.0			
52+11.7	53+11.5	RT		99.8			
55+02.7	302+00.0	RT		325.0			
300+24.3	300+48.6	LT		32.0			
57+92.2	60+16.5	LT		228.0			
<b>TOTAL</b>		<b>4033</b>	<b>1293</b>	<b>1382.7</b>	<b>3631</b>	<b>217</b>	

SCHEDULE OF TEMPORARY EROSION CONTROL			
28000250 TEMPORARY EROSION CONTROL SEEDING			
28000400 PERIMETER EROSION BARRIER			
28000500 INLET AND PIPE PROTECTION			
LOCATION	TEMP. EROSION CONTROL SEEDING	PERIMETER EROSION BARRIER	INLET AND PIPE PROTECTION
	LB	FOOT	EACH
44+45 to 46+89 RT	40		
44+45 to 47+09 LT	60		
47+24 to 50+70 RT	60		
47+45 to 50+90 LT	80		
51+57 to 53+12 RT	40		
53+12 to 302+50 RT	80		
51+70 to 53+20 LT	40		
53+20 to 202+00 LT	120		
302+00 to 70+95 RT	120		
202+00 to 70+95 LT	120		
44+45 to 46+89 RT		275	
44+45 to 47+09 LT		307	
47+24 to 50+70 RT		443	
47+45 to 50+90 LT		429	
51+57 to 302+50 RT		709	
51+70 to 202+00 LT		645	
302+00 to 70+95 RT		1453	
202+00 to 70+95 LT		1464	
69+61			1
<b>TOTAL</b>	<b>760</b>	<b>5725</b>	<b>1</b>

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE OF QUANTITIES**

SCALE: VERT. HORIZ. DATE 08/25/2005 DRAWN BY SWEET CHECKED BY ZELINSKAS