

SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6371	93-00295-02-PV	MCLEAN	117	4
STA.		TO STA.		
ILLINOIS				
CONTRACT NO. 87267				

CODE NO.	ITEM	SAFETY CODE		2A	2A	1F	Y060	Y060
		CONSTRUCTION CODE		J000	J000	Y031	Y060	Y060
		UNIT	TOTAL QUANTITY	HAMILTON ROAD 80% FEDERAL 20% CITY	MORRIS AVENUE 80% FEDERAL 20% CITY	TRAFFIC SIGNALS 80% FEDERAL 20% CITY	WATER MAIN ** 100% CITY	SANITARY SEWER ** 100% CITY
				(1)	(2)		(1)	(2)
* 20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	836	554	220			62
* 20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	1052	728	306			18
20200100	EARTH EXCAVATION	CU YD	28696	23041	5655			
* 20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1325	1043	282			
20800150	TRENCH BACKFILL	CU YD	8591	1224	340		2715	4312
* 20900330	GRANULAR BACKFILL	TON	2717	2138	579			
* 21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	3458	2123	1335			
* 25000110	SEEDING, CLASS 1A	ACRE	6.5	4.0	2.5			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	585	360	225			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	585	360	225			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	585	360	225			
* 25100125	MULCH, METHOD 3	ACRE	6.5	4.0	2.5			
25200100	SODDING	SQ YD	305	53	252			
25200200	SUPPLEMENTAL WATERING	UNIT	5	1	4			
* 25300910	SALVAGING AND TRANSPLANTING TREES, SPECIAL	EACH	61	44	17			
* 28000255	TEMPORARY EROSION CONTROL SEEDING	ACRE	6.5	4.0	2.5			
28000300	TEMPORARY DITCH CHECKS	EACH	10		10			
28000400	PERIMETER EROSION BARRIER	FOOT	4603	2563	2040			
28000500	INLET AND PIPE PROTECTION	EACH	4	3	1			
* 28000510	INLET FILTERS	EACH	68	44	24			
28100229	STONE RIPRAP, CLASS B5	TON	10	10				
28200200	FILTER FABRIC	SQ YD	11	11				
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	27699	19184	8515			
35100500	AGGREGATE BASE COURSE, TYPE A 6"	SQ YD	4983	4766	217			
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	17	14	3			
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	776	451	325			
40600300	AGGREGATE (PRIME COAT)	TON	4		4			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	1		1			
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	75	19	56			
* 40600990	TEMPORARY RAMP	SQ YD	42	10	32			
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	616	287	329			
42000200	PORTLAND CEMENT CONCRETE PAVEMENT 7"	SQ YD	7290		7290			
42000300	PORTLAND CEMENT CONCRETE PAVEMENT 8"	SQ YD	17364	17364				
42001300	PROTECTIVE COAT	SQ YD	27128	18844	8284			
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	1952	1421	531			

*SEE SPECIAL PROVISIONS
 **NON-PARTICIPATING WORK
 + SPECIALTY ITEM

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

DATE : 3-05
 DRAWN BY : J.L.B.
 CHECKED BY : R.L.H.

SCALE : NONE