

# SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6371	93-00295-02-PV	MCLEAN	117	7
STA.		TO STA.		
		ILLINOIS		
CONTRACT NO. 87267				

CODE NO.	ITEM	SAFETY CODE		2A	2A	1F	Y060	Y060
		CONSTRUCTION CODE		J000	J000	Y031	Y060	Y060
		UNIT	TOTAL QUANTITY	HAMILTON ROAD 80% FEDERAL 20% CITY (1)	MORRIS AVENUE 80% FEDERAL 20% CITY (2)	TRAFFIC SIGNALS 80% FEDERAL 20% CITY	WATER MAIN ** 100% CITY	SANITARY SEWER ** 100% CITY (2)
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	4040	4040				
70300560	PAVEMENT MARKING TAPE, TYPE III 12"	FOOT	63	63				
70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	36	36				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1021	1021				
+ 72000100	SIGN PANEL - TYPE 1	SQ FT	20			20		
+ 72000200	SIGN PANEL - TYPE 2	SQ FT	50			50		
+ 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	47		47			
+ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2909	502	2407			
+ 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	71		71			
+ 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	201	2	199			
+ 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	12		12			
+* 78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	437	250	187			
+* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	5058		5058			
+* 78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	9507	9134	373			
+* 78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	745	745				
+* 78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	1309	602	707			
+* 78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	243	111	132			
+* 80400105	ELECTRIC SERVICE INSTALLATION, SPECIAL	EACH	1	1				
+* 80500100	SERVICE INSTALLATION, TYPE A	EACH	1			1		
+* 80500200	SERVICE INSTALLATION, TYPE B	EACH	1			1		
+ 80803560	TRAFFIC SIGNAL WOOD POLE, 30 FT., CLASS 4	EACH	1			1		
+* 81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	787	597		190		
+* 81016400	CONDUIT IN TRENCH, 1/4" DIA., HIGH DENSITY POLYETHYLENE, COILABLE	FOOT	164			164		
+* 81016600	CONDUIT IN TRENCH, 2" DIA., HIGH DENSITY POLYETHYLENE, COILABLE	FOOT	2720			2720		
+* 81016700	CONDUIT IN TRENCH, 2 1/2" DIA., HIGH DENSITY POLYETHYLENE, COILABLE	FOOT	120			120		
+* 81017000	CONDUIT IN TRENCH, 4" DIA., HIGH DENSITY POLYETHYLENE, COILABLE	FOOT	113			113		
+* 81017100	CONDUIT IN TRENCH, 5" DIA., HIGH DENSITY POLYETHYLENE, COILABLE	FOOT	111			111		
+* 81306100	JUNCTION BOX (SPECIAL)	EACH	10			10		
+* 81400400	CONCRETE HANDHOLE	EACH	6			6		
+* 81400600	CONCRETE DOUBLE HANDHOLE	EACH	1			1		
+ 81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	4015	597		3418		
+ 81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	1485			1485		
+ 82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	4			4		
+* 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	4		1			3
+* 85704804	FULL-ACTUATED CONTROLLER, STANDARD SEQUENCE IV, 8 PHASES, IN TYPE IV CABINET	EACH	1			1		

\*SEE SPECIAL PROVISIONS  
 \*\*NON-PARTICIPATING WORK  
 + SPECIALTY ITEM

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SUMMARY OF QUANTITIES

SCALE : NONE  
 DATE : 3-05  
 DRAWN BY : J.L.B.  
 CHECKED BY : R.L.H.