

SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6371	93-00295-02-PV	MCLEAN	117	9
STA.		TO STA.		
ILLINOIS				

CONTRACT NO. 87267

CODE NO.	ITEM	SAFETY CODE		2A	2A	1F		
		CONSTRUCTION CODE		J000	J000	Y031	Y060	Y060
		UNIT	TOTAL QUANTITY	HAMILTON ROAD 80% FEDERAL 20% CITY (1)	MORRIS AVENUE 80% FEDERAL 20% CITY (2)	TRAFFIC SIGNALS 80% FEDERAL 20% CITY	WATER MAIN** 100% CITY	SANITARY SEWER** 100% CITY (2)
+ B2004116	TREE, MALUS PRAIRIFIRE (PRAIRIFIRE CRABAPPLE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	3	2	1			
+ B2005216	TREE, MALUS SUTYZAM (SUGAR TYME CRABAPPLE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	2	2				
+ B2006316	TREE, SYRINGA RETICULATA IVORY SILK (IVORY SILK JAPANESE TREE LILAC), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	6	2	4			
+ D2000148	EVERGREEN, ABIES CONCOLOR (WHITE FIR), 4' HEIGHT, BALLED AND BURLAPPED	EACH	6	2	4			
+ D2001748	EVERGREEN, PICEA ABIES (NORWAY SPRUCE), 4' HEIGHT, BALLED AND BURLAPPED	EACH	5	4	1			
+ D2002048	EVERGREEN, PICEA OMORIKA (SERBIAN SPRUCE), 4' HEIGHT, BALLED AND BURLAPPED	EACH	6	4	2			
* X0321905	STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE, 12"	FOOT	250	61	189			
* X0321906	STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE, 15"	FOOT	47		47			
* X0321907	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 12"	FOOT	123	98	25			
* X0321908	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 15"	FOOT	20	20				
* X0321909	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 24"	FOOT	26	26				
* X0322630	CONCRETE ENCASEMENTS	EACH	1					1
* X0488100	REMOVING EXISTING SEPTIC TANK	EACH	4					4
* X4066490	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, IL 9.5L (LOW ESAL)	TON	183	183				
* X6020125	RESTRICTED DEPTH INLET TYPE B, TYPE 3 FRAME AND GRATE	EACH	3		3			
+ X8801310	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	6			6		
+ X8801345	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED	EACH	4			4		
+ X8801350	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	4			4		
+ X8810400	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED, SPECIAL	EACH	4			4		
+ X8850106	INDUCTIVE LOOP DETECTOR, RACK MOUNTED	EACH	18			18		
+ X8850107	INDUCTIVE LOOP DETECTOR, RACK MOUNT WITH SYSTEM OUTPUT	EACH	10			10		
* XX000613	MODULAR BLOCK RETAINING WALL	SQ FT	2328	2328				
+ XX002161	ABANDON EXISTING WATER MAIN	EACH	1				1	
+ XX003327	CONDUIT AUGERED 4", HIGH DENSITY POLYETHYLENE, COILABLE	FOOT	130			130		
* XX003503	FLARED END SECTION REMOVAL	EACH	1	1				
+ XX004205	OUTSIDE DROP CONNECTION	EACH	4					4
+ XX005470	RESTRICTED DEPTH MANHOLES, 4' DIAMETER, TYPE 37M GRATE	EACH	1	1				
+ XX005476	DUCTILE IRON WATER MAIN 12" RESTRAINED JOINT TYPE	FOOT	188				188	
+ XX005478	DUCTILE IRON WATER MAIN 6" RESTRAINED JOINT TYPE	FOOT	154				154	
+ XX005479	DUCTILE IRON WATER MAIN 8" RESTRAINED JOINT TYPE	FOOT	63				63	
+ XX005480	DUCTILE IRON WATER MAIN 16" RESTRAINED JOINT TYPE	FOOT	962				962	
* XX005483	RESTRICTED DEPTH INLET TYPE B TYPE 1 FRAME OPEN LID	EACH	3		3			
* Z0000990	AGGREGATE FOR TEMPORARY ACCESS	TON	529	85	420			24
+ Z0007601	BUILDING REMOVAL NO. 1	L SUM	1		1			
* Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.45	0.30	0.05	0.10	0.10

* SEE SPECIAL PROVISIONS
 ** NON-PARTICIPATING WORK
 + SPECIALTY ITEM

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

DATE : 3-05
 DRAWN BY : J.L.B.
 CHECKED BY : R.L.H.

SCALE : NONE