

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
750	(112,113) Y, WRS	FAYETTE	178	4
STA.	TO STA.			
FED. ROAD DIST. NO. 7	ILLINOIS		FED. AID PROJECT	

CONTRACT NO. 94927

SUMMARY OF QUANTITIES			80% FED, 20% STATE	CONSTRUCTION TYPE CODE	
CODE	ITEM	UNIT	TOTAL QUANTITIES	STA 120+00.00 TO 436+00.00	
				1000	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	3	3	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	6763	6763	
70300220	TEMPORARY PAVEMENT MARKING LINE - 4"	FOOT	100771	100771	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ. FT.	2254	2254	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	100771	100771	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	404	404	
* 78200405	GUARDRAIL MARKERS	EACH	20	20	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	8	8	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	404	404	
X0322263	CULVERT DROP BOX	EACH	6	6	
X0322923	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	2020	2020	
X0349800	CONCRETE HEADWALL FOR PIPE UNDERDRAIN REMOVAL	EACH	4	4	
X3550010	BITUMINOUS BASE COURSE SUPERPAVE	TON	618	618	
X3560130	BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 9"	SQ YD	21330	21330	
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE MIX "C" N50	TON	7162	7162	
X4066616	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL 19.0, N70	TON	658	658	
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE, N50	TON	4777	4777	
X4080020	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE, N50	TON	180	180	
X6013700	PIPE UNDERDRAIN REMOVAL (SPECIAL)	FOOT	1600	1600	
Z0041500	PLUG EXISTING CULVERTS	EACH	2	2	
Z0076600	TRAINEES	HOUR	500		500

• DENOTES SPECIALTY ITEMS

PL AN	DATE
NO.	
BY	
CHECKED	
ALIGNED	
FILED	
NAME	

PL AN	DATE
NO.	
BY	
CHECKED	
ALIGNED	
FILED	
NAME	

REVISIONS	
NAME	DATE
KdG	3/02/05
KdG	5/10/05
KdG	8/26/05

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
**SHEET 2 OF 2 SHEETS**  
 F.A.P. 750 (IL. RTE. 185)  
 SECTION 112,113 - FAYETTE CO.  
 SCALE: DRAWN BY CRO  
 DATE JULY 22, 2005 CHECKED BY RCY

Rev.