

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0044						CODE NO	ITEM	UNIT	TOTAL QUANTITIES						
20200100	EARTH EXCAVATION	CU YD	89.5	89.5															
*21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	963	963															
21400100	GRADING AND SHAPING DITCHES	FOOT	250	250															
*25000210	SEEDING, CLASS 2A	ACRE	0.07	0.07															
*25000400	NITROGEN FERTILIZER NUTRIENT	POUND	15	15															
*25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	15	15															
*25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	15	15															
*25100630	EROSION CONTROL BLANKET	SQ YD	963	963															
*25200100	SODDING	SQ YD	620	620															
28000400	PERIMETER EROSION BARRIER	FOOT	758.5	758.5															
28000500	INLET AND PIPE PROTECTION	EACH	2	2															
55100900	STORM SEWER REMOVAL 18"	FOOT	198	198															
55101200	STORM SEWER REMOVAL 24"	FOOT	125	125															
55101400	STORM SEWER REMOVAL 30"	FOOT	130	130															
60204505	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE B GRATE	EACH	3	3															
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1															
60224446	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2															
60500040	REMOVING MANHOLES	EACH	2	2															
60500050	REMOVING CATCH BASINS	EACH	1	1															
67100100	MOBILIZATION	L SUM	1	1															
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6															
70100450	TRAFFIC CONTROL & PROTECTION, STD. 701201	L SUM	1	1															
X5521500	STORM SEWERS JACKED IN PLACE, 42" SPECIAL	FOOT	291	291															
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	104	104															
Z0056628	STORM SEWERS (WATERMAIN REQUIREMENTS), 48"	FOOT	453	453															
Z0068412	STEEL CASINGS, 54"	FOOT	291	291															

*SPECIALTY ITEMS

FILE NAME =	USER NAME = jaysa	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	I-55 EAST OF IL-53 DRAINAGE IMPROVEMENT SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\work\work\jaysa\dms89282\0107405-stl-drain.dgn	PLOT SCALE = 50,000' / 1" =	DRAWN -	REVISED -			55	29T-1	WILL	19	3	
	PLOT DATE = 8/29/2011	CHECKED -	REVISED -			CONTRACT NO. 60A56					
		DATE -	REVISED -			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT					

Rev.