

**SUMMARY OF QUANTITIES**

**CONSTRUCTION TYPE CODE**

**EMERGENCY VEHICLE PREEMPTION**  
~~100% VILLAGE OF SUGAR GROVE 0021~~

CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE						
				ROADWAY	STRUCTURES	LIGHTING	TRAFFIC SIGNALS			INTERCONNECT
							GALENA & IL ROUTE 56 W. RAMPS	GALENA & IL ROUTE 56 E. RAMPS		
0004	0011	0021	0021	0021	0021	0021				
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1	-	-	-	-	-	-
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	1	1	-	-	-	-	-	-
60236900	INLETS, TYPE A, TYPE 12 FRAME AND GRATE	EACH	1	1	-	-	-	-	-	-
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	4	4	-	-	-	-	-	-
60262700	INLETS TO BE RECONSTRUCTED	EACH	3	3	-	-	-	-	-	-
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	5	5	-	-	-	-	-	-
60609200	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.12	FOOT	3541	3541	-	-	-	-	-	-
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	18,819	18,819	-	-	-	-	-	-
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	738	738	-	-	-	-	-	-
60624600	CORRUGATED MEDIAN	SQ FT	193	193	-	-	-	-	-	-
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	638	638	-	-	-	-	-	-
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1	-	-	-	-	-	-
* 63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	1	1	-	-	-	-	-	-
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2	-	-	-	-	-	-
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2	-	-	-	-	-	-
63200310	GUARDRAIL REMOVAL	FOOT	397	397	-	-	-	-	-	-
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7	7	-	-	-	-	-	-
67100100	MOBILIZATION	L SUM	1	1	-	-	-	-	-	-
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	130	130	-	-	-	-	-	-
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	4	-	-	1	1	-	-
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1616	1616	-	-	-	-	-	-
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	146	146	-	-	-	-	-	-
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	37,710	37,710	-	-	-	-	-	-
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	775	775	-	-	-	-	-	-
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1573	1573	-	-	-	-	-	-
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	372	372	-	-	-	-	-	-
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	6010	6010	-	-	-	-	-	-
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	270	270	-	-	-	-	-	-

\* SPECIALTY ITEM

\* Specialty Item

Rev. 11-9-11

FILE NAME = P:\2010\ME\10012.PT\B156-16.Galena\CADD\Shs\03-D160K76-shs-Galena-500.dgn  
 PLOT SCALE = 1:2000 / IN.  
 SHEET NAME = Millennium Professional Services



200 22ND Street, Suite 216, Lombard, IL 60148  
 630.705.0110 voice, 630.839.2566 fax  
 www.mps-il.com  
**MILLENNIA PROFESSIONAL SERVICES**

DESIGNED - CJD	REVISED -
DRAWN - CJD	REVISED -
CHECKED - TVN	REVISED -
DATE - 8/30/2011	REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**GALENA BOULEVARD**

**SUMMARY OF QUANTITIES**

SCALE: NTS SHEET NO. 3 OF 6 SHEETS STA. TO STA.

F.A.P. RTE. 573	SECTION 61HB-1-R	COUNTY KANE	TOTAL SHEETS 110	SHEET NO. 5
CONTRACT NO. 60K76			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	