

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE						
				ROADWAY 0004	STRUCTURES 0011	LIGHTING 0021	TRAFFIC SIGNALS			EMERGENCY VEHICLE PREEMPTION 100% VILLAGE OF SUGAR GROVE 0021
							GALENA & IL ROUTE 56 RAMP-C 0021	GALENA & IL ROUTE 56 RAMP A/B 0021	INTERCONNECT 0021	
* 81400300	DOUBLE HANDHOLE	EACH	2	-	-	-	1	1	-	-
* 81603090	UNIT DUCT, 600V, 3-1C NO.4, 1/C NO.6 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	3200	-	-	3200	-	-	-	-
* 81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	1000	-	-	1000	-	-	-	-
* 81702140	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4	FOOT	3000	-	-	3000	-	-	-	-
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	6070	-	-	3500	875	1120	575	-
* 82102200	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 200 WATT	EACH	4	-	-	4	-	-	-	-
* 83600350	LIGHT POLE FOUNDATION, METAL, 11" BOLT CIRCLE, 8" X 6'	EACH	1	-	-	1	-	-	-	-
* 84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	2	-	-	2	-	-	-	-
* 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	10	-	-	10	-	-	-	-
* 85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1	-	-	-	1	-	-	-
* 85700300	FULL-ACTUATED CONTROLLER AND TYPE V CABINET	EACH	1	-	-	-	-	1	-	-
* 86000100	MASTER CONTROLLER	EACH	1	-	-	-	-	-	1	-
* 86200120	UNINTERRUPTIBLE POWER SUPPLY	EACH	2	-	-	-	1	1	-	-
* 86400100	TRANSCEIVER - FIBER OPTIC	EACH	2	-	-	-	1	1	-	-
* 87100020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	1350	-	-	-	-	-	1350	-
* 87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	1350	-	-	-	-	-	1350	-
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	760	-	-	-	-	-	1350	-
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	5400	-	-	-	2320	3080	-	-
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	410	-	-	-	-	410	-	-
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	4340	-	-	-	2170	2170	-	-
* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	315	-	-	-	125	190	-	-
* 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	1970	-	-	-	890	1080	-	-
* 87502480	TRAFFIC SIGNAL POST, 14 FT.	EACH	10	-	-	-	6	4	-	-
* 87502500	TRAFFIC SIGNAL POST, 16 FT.	EACH	2	-	-	-	-	2	-	-
* 87502520	TRAFFIC SIGNAL POST, 10 FT.	EACH	1	-	-	-	-	-	-	-
* 87700190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT.	EACH	1	-	-	-	1	-	-	-
* 87702880	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 30 FT.	EACH	1	-	-	-	1	-	-	-
* 87702960	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 46 FT.	EACH	1	-	-	-	1	-	-	-
* 87702980	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 50 FT.	EACH	1	-	-	-	-	1	-	-

EMERGENCY VEHICLE PREEMPTION
100% VILLAGE OF SUGAR GROVE
0021

* SPECIALTY ITEM

FILE NAME = P:\2010\ME10012.P\FB156-16.Galena\CADD\Shets\03-D160K76-sht-Galena-500.dgn
PLOT SCALE = 1/8" = 1'-0"
USER NAME = Millennium Professional Services



200 22ND Street, Suite 216, Lombard, IL 60148
630.705.0110 voice, 630.839.2566 fax
www.mps-il.com
MILLENNIA PROFESSIONAL SERVICES

DESIGNED - CJD	REVISED -
DRAWN - CJD	REVISED -
CHECKED - TWN	REVISED -
DATE - 8/30/2011	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

GALENA BOULEVARD

SUMMARY OF QUANTITIES

F.A.P. RTE. 573	SECTION 61HB-1-R	COUNTY KANE	TOTAL SHEETS 110	SHEET NO. 7
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60K76	

SCALE: NTS SHEET NO. 5 OF 6 SHEETS STA. TO STA.

Rev 11-9-11

Rev.