

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE						
				ROADWAY	STRUCTURES	LIGHTING	TRAFFIC SIGNALS			EMERGENCY VEHICLE PREEMPTION
							GALENA & IL ROUTE 56 RAMP-C	GALENA & IL ROUTE 56 RAMP A/B	INTERCONNECT	
0004	0011	0021	0021	0021	0021	0021	100% VILLAGE OF SUGAR GROVE 0021			
* 87704516	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 48 FT. AND 30 FT.	EACH	1	-	-	-	-	1	-	-
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	48	-	-	-	24	24	-	-
* 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	8	-	-	-	4	4	-	-
* 87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	20	-	-	-	20	-	-	-
* 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	42	-	-	-	13	29	-	-
* 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	12	-	-	-	6	6	-	-
* 88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	10	-	-	-	6	4	-	-
* 88030210	SIGNAL HEAD, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2	-	-	-	1	1	-	-
* 88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	2	-	-	-	-	2	-	-
* 88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	12	-	-	-	6	6	-	-
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	15	-	-	-	7	8	-	-
* 88600100	DETECTOR LOOP, TYPE 1	FOOT	895	-	-	-	385	510	-	-
* 88700200	LIGHT DETECTOR	EACH	4	-	-	-	-	-	-	4
* 88700300	LIGHT DETECTOR AMPLIFIER	EACH	2	-	-	-	-	-	-	2
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	312	-	312	-	-	-	-	-
Δ X5539700	STORM SEWERS TO BE CLEANED	FOOT	410	410	-	-	-	-	-	-
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	-	-	-	-	-	-
* X8180060	AERIAL CABLE, 3-1/C NO. 2, ALUMINUM, WITH MESSENGER WIRE	FOOT	150	-	-	150	-	-	-	-
* X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	760	-	-	-	-	-	-	760
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	793	793	-	-	-	-	-	-
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	65	-	65	-	-	-	-	-
Z0001903	STRUCTURAL STEEL REMOVAL	POUND	7980	-	7980	-	-	-	-	-
Z0003500	BEAM STRAIGHTENING	EACH	3	-	3	-	-	-	-	-
Z0004552	APPROACH SLAB REMOVAL	SQ YD	574	-	574	-	-	-	-	-
Z0007112	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES	L SUM	1	-	1	-	-	-	-	-
Z0010501	CLEANING AND PAINTING STEEL BRIDGE NO. 1	L SUM	1	-	1	-	-	-	-	-
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SO FT	292	-	292	-	-	-	-	-

Δ NON-PARTICIPATING (100% STATE)
* Specialty Items

FILE NAME = P:\2010\ME10012.PT\B156-16.Galena\CADD\Shets\03-D160K76-sht-Galena-500.dgn
PLOT SCALE = 1/8" = 1'-0"
USER NAME = Millennium Professional Services



200 22ND Street, Suite 216, Lombard, IL 60148
630.705.0110 voice, 630.839.2566 fax
www.mps-il.com

MILLENNIA PROFESSIONAL SERVICES

DESIGNED - CJD	REVISED -
DRAWN - CJD	REVISED -
CHECKED - TVN	REVISED -
DATE - 8/30/2011	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

GALENA BOULEVARD

SUMMARY OF QUANTITIES

SCALE: NTS SHEET NO. 6 OF 6 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
573	61HB-1-R	KANE	110	8
CONTRACT NO. 60K76				