

**SUMMARY OF QUANTITIES**

**CONSTRUCTION TYPE CODE**

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
				ROADWAY HSIP 90% FED 10% STATE 0005	PED SIGNAL 50% STATE 25% COUNTY 0021	SIDEWALK 80% STATE 20% CITY 0021
* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	240		240	-
* 81400100	HANDHOLE	EACH	1		1	-
* 81603200	UNIT DUCT, 600V, 3-1C NO.2, 1/C NO.4 GROUND, (EPR-TYPE RHW), 1 1/4" DIA. POLYETHYLENE	FOOT	430		430	-
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	650		650	-
* 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	2		2	-
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 2C	FOOT	475		475	-
* 88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	4		4	-
* 88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	1		1	-
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	97	97		-
* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	6		6	-
* 89502376	REBUILD EXISTING HANDHOLE	EACH	1		1	-
* 89502380	REMOVE EXISTING HANDHOLE	EACH	1		1	-
<del>89900110</del>	<del>TREE, ACER X FREEMANII AUTUMN BLAZE (AUTUMN BLAZE FREEMAN MAPLE) 3" CALIPER, BALLED AND BURLAPPED</del>	<del>EACH</del>	<del>3</del>			
Δ X5539700	STORM SEWERS TO BE CLEANED	FOOT	144	144		
X6061460	PAVED DITCH (SPECIAL)	FOOT	166	166		
X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1		
* X8360120	LIGHT POLE FOUNDATION, SPECIAL	EACH	2	2		
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	1223	1223		
Z0013302	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	575	575		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	2	2		
Δ Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	18	18		
Z0018700	DRAINAGE STRUCTURE TO BE REMOVED	EACH	2	2		
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	104	104		
* Z0033024	MAINTAIN EXISTING LIGHTING SYSTEM	L SUM	1	1		
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1		

Δ Non-participating (100% State)

\* SPECIALTY ITEM

Rev. 11-7-11

FILE NAME = P:\2009\ME09006\_Ver-Yar-Phil\CADD\W022\_US34\Shets\03-500\ht-shet-US34.dgn  
 PLOT SCALE = 1:1000 / IN.  
 USER NAME = PhilTurner Professional Services



200 22ND Street, Suite 216, Lombard, IL 60148  
 630.785.0110 voice, 630.839.2566 fax  
 www.mps-il.com

**MILLENNIA PROFESSIONAL SERVICES**

DESIGNED -	CJD	REVISED -	
DRAWN -	CJD	REVISED -	
CHECKED -	TVN	REVISED -	
DATE -	6/1/2011	REVISED -	

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**US ROUTE 34  
 AT NORTH AURORA ROAD /RAYMOND DRIVE**

**SUMMARY OF QUANTITIES**

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	652X-N-3	DUPAGE	34	4
CONTRACT NO.			60L22	

SCALE: NTS SHEET NO. 1 OF 2 SHEETS STA. TO STA.

FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT

P:\2009\ME09006\_Ver-Yar-Phil\CADD\W022\_US34\Shets\03-500\ht-shet-US34.dgn