

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
				ROADWAY 90% FED. 10% STATE	ROADWAY 90% FED. 10% STATE	Interconnect 90% Fed. 10% State	River Rd TRAFFIC SIGNAL 90% FED. 10% STATE 6.7% COUNTY	EMERGENCY VEHICLE PREEMPTION 100% CITY					Pactage Rd. Traffic Signal 90% Fed. 10% State 25% Will Co 25% City of Wilmington 0021	ROADWAY	ROADWAY	MULTI-USE PATH	TRAFFIC SIGNAL
				0004	0005	0021	0021	0021				0004	0005	0028	0021	0021	
*88030220	SIGNAL HEAD, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1			1											
*88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	4			4											
*88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	10			6		4									
*88500100	INDUCTIVE LOOP DETECTOR	EACH	12			6		6									
*88600100	DETECTOR LOOP, TYPE I	FOOT	811			776		35									
*88700200	LIGHT DETECTOR	EACH	2					2									
*88700300	LIGHT DETECTOR AMPLIFIER	EACH	1					1									
*88800100	PEDESTRIAN PUSH-BUTTON	EACH	4			4											
*89501410	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, PHASING UNIT	EACH	1					1									
*89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1					1									
*A2002920	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	12	12													
*B2001666	TREE, CRATAEGUS CRUSGALLI INERMIS (THORN LESS COCKSPUR HAWTHORN), 6' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED	EACH	9	9													
*K0029634	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	2	2													
*87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	3125			3125											
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	1	1													
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	3	3													
X4024000	TEMPORARY ACCESS (FIELD ENTRANCE)	EACH	1	1													
X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), 1L-4.75, N50	TON	875	470	405												
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	0.75	0.25												
*87100010	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	3160			3160											
*87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6, 1C	FOOT	1080			1080											
*X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	625					625									
Z0001050	AGGREGATE SUBGRADE 12"	SO YD	7825	7825													
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1													
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	77.1	77.1													
*Z0033056	OPTIMIZE TRAFFIC SIGNAL SYSTEM	EACH	1			1											
Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	1250	1250													

* SPECIALTY ITEMS