



016-1045 I-55 N.B. Ramp to US 41 S.B.

Span Count From West to East / South  
Span 1 between Pier E13 and ES1

**PLAN**

Span #	Lane 1	
	Partial	Full
1	0	1 @ 3 ft x 3 ft = 1 SY
2	1 @ 3 ft x 3 ft = 1 SY	0
3	0	0
4	2 @ 3 ft x 3 ft = 2 SY	0
5	1 @ 3 ft x 3 ft = 1 SY	1 @ 3 ft x 3 ft = 1 SY
6	3 @ 3 ft x 3 ft = 3 SY	1 @ 3 ft x 3 ft = 1 SY
7	2 @ 3 ft x 3 ft = 2 SY	0
8	1 @ 3 ft x 3 ft = 1 SY	0
	1 @ 4 ft x 4 ft = 2 SY	
9	0	0
10	0	1 @ 6 ft x 6 ft = 4 SY
11	0	0
12	1 @ 3 ft x 3 ft = 1 SY	0
TOTAL	13 SF	7 SY

TOTAL : PARTIAL DEPTH GRAND TOTAL = 116 SF  
POTENTIAL FULL DEPTH GRAND TOTAL = 18 SF

**STRUCTURE NO. 016-1045**

**LIMITS OF STRUCTURE NO. 016-1045**

I-55 @ Lake Shore Drive

FILE NAME = I:\102908\_I-55\STRUCTURAL\sheet\1045\016037-15-conc\_patching.dgn

<p><b>CHRISTIAN-ROGE &amp; ASSOCIATES, INC.</b></p>	USER NAME == IDOT	DESIGNED - J.C.N./B.N.S.	REVISED -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>DECK CONCRETE PATCHING</b> <b>STRUCTURE NO. 016-1045</b>	F.A.I. RTE. 55	SECTION 2011-031-BR	COUNTY COOK	TOTAL SHEETS 41	SHEET NO. 15
	PLOT SCALE = 50,0000' / IN.	CHECKED - B.N.S./J.C.N.	REVISED -			SHEET NO. S15 OF S41 SHEETS				
	PLOT DATE == 10/12/2011	DRAWN - F.M.	REVISED -			CONTRACT NO. 60P37				
	DATE - OCTOBER 12, 2011	REVISED -	ILLINOIS FED. AID PROJECT							