

SUMMARY OF QUANTITIES				100% STATE			07C0L		07P0L
CODE NO.	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY	TRAFFIC SIGNALS	STRUCTURES	80% STATE 20% LILY LAKE SIDEWALK	100% ELBURN & COUNTRYSIDE FPD	
			URBAN	0004	0021	0005	0021	0021	
* 87700200	STEEL MAST ARM ASSEMBLY AND POLE, 32 FT.	EACH	1		1				
<del>87700250</del>	<del>STEEL MAST ARM ASSEMBLY AND POLE, 42 FT.</del>	<del>EACH</del>	<del>1</del>		<del>1</del>				
* 87700260	STEEL MAST ARM ASSEMBLY AND POLE, 44 FT.	EACH	2		2				
* 87700270	STEEL MAST ARM ASSEMBLY AND POLE, 46 FT.	EACH	1		1				
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	24		24				
* 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4		4				
* 87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	14		14				
* 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	39		39				
* 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	1		1				
* 88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2		2				
* 88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	7		7				
* 88030220	SIGNAL HEAD, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	3		3				
* 88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	1		1				
* 88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	6		6				
* 88102757	PEDESTRIAN SIGNAL HEAD, LED, 3-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2		2				
* 88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	8		8				
* 88600700	PREFORMED DETECTOR LOOP	FOOT	740		740				
* 88700200	LIGHT DETECTOR	EACH	2					2	
* 88700300	LIGHT DETECTOR AMPLIFIER	EACH	1					1	
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	12		12				
* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	10		10				
<del>88502375</del>	<del>REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT</del>	<del>EACH</del>	<del>1</del>		<del>1</del>				
K0029632	WEED CONTROL, NON-SELECTIVE AND NON-RESIDUAL	GALLON	0.6	0.6					
<del>K1004505</del>	<del>PRUNING FOR SAFETY AND EQUIPMENT CLEARANCE</del>	<del>L SUM</del>	<del>1</del>	<del>1</del>					
X0325833	WICK DRAINS	FOOT	30,200	30,200					
X0325834	HORIZONTAL STRIP DRAINS	FOOT	2,450	2,450					
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	2	2					
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	8	8					
X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1					
* X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	279					279	
Z0001050	AGGREGATE SUBGRADE, 12"	SQ YD	21,126	21,126					
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1					
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	103	103					
Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	1,865	1,865					
Z0062456	TEMPORARY PAVEMENT	SQ YD	2,544	2,544					
Z0064800	SELECTIVE CLEARING	UNIT	25	25					
Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	13,286	13,286					
<del>89502400</del>	<del>REMOVE EXISTING FLASHING BEALON INSTALLATION COMPLETE</del>	<del>EACH</del>	<del>1</del>		<del>1</del>				
X8500100	TEMPORARY FLASHING BEALON INSTALLATION	EACH	1		1				

\* DENOTES SPECIALTY ITEM

FILE NAME =	USER NAME = .USER.	DESIGNED - AR	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>IL 64 AT IL 47 INTERSECTION IMPROVEMENTS SUMMARY OF QUANTITIES</b>	F.A.P. RTE. 307	SECTION 126N-1	COUNTY KANE	TOTAL SHEETS 156	SHEET NO. 8	Rev.	
*FILEL*	PLOT SCALE = 50,000 ft / IN.	DRAWN - AR	REVISED -			SCALE:	SHEET NO. 5 OF 5 SHEETS	STA.	TO STA.	CONTRACT NO. 62278		ILLINOIS FED. AID PROJECT
	PLOT DATE = 9/1/2011	CHECKED - RS	REVISED -									
		DATE - 09-01-2011	REVISED -									