


- NOTES:**
- EXISTING LIGHTING UNITS AND CONTROLLER AT 124TH STREET SHALL REMAIN TO PROVIDE TEMPORARY LIGHTING WHILE PROPOSED LIGHTING IS INSTALLED. AERIAL CABLE SHALL BE CONNECTED TO THE EXISTING LIGHTING UNITS SO THAT THE PROPOSED UNIT DUCT CAN BE INSTALLED.
  - AERIAL CABLE AND TEMPORARY WOOD POLES SHALL BE REMOVED WHEN PROPOSED LIGHTING IS OPERATIONAL. THE COST SHALL BE INCLUDED IN PAY ITEM REMOVAL OF TEMPORARY LIGHTING UNIT.
  - THE COST FOR REMOVAL OF EXISTING DUCT AND CONDUCTORS (AS REQUIRED BY THE ENGINEER) SHALL BE INCLUDED IN PAY ITEM REMOVAL OF TEMPORARY LIGHTING UNIT.



LTG-06

<b>MORRIS ENGINEERING, INC.</b> <small>5700 S. LINCOLN BLVD. SUITE 100, LITTLE ROCK, AR 72202          PHONE: (501) 771-0770</small>	<b>AMES Engineering, Inc.</b> <small>CONSULTING ENGINEERS          1341 Warren Avenue          Deshler's Tower, E. 85515          (816) 737-1887 FAX: (816) 470-8481 (F)          www.ameseng.com</small>
---	--

FILE NAME	USER NAME	DESIGNED	REVISED
#FILE#	#USER#	- BL	-
		DRAWN	REVISED
		- RV	-
		CHECKED	REVISED
		- SA	-
		DATE	REVISED
		- 06-03-11	-

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**CITY OF PALOS HEIGHTS LIGHTING IMPROVEMENTS  
TEMPORARY / REMOVAL PLAN**

F.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
348	09-00046-00-LT	COOK	20	7
CONTRACT NO. 63518				
<small>ILLINOIS FED. AID PROJECT</small>				