


**NOTES:**

1. EXISTING LIGHTING UNITS AND CONTROLLER AT 124TH STREET SHALL REMAIN TO PROVIDE TEMPORARY LIGHTING WHILE PROPOSED LIGHTING IS INSTALLED. AERIAL CABLE SHALL BE CONNECTED TO THE EXISTING LIGHTING UNITS SO THAT THE PROPOSED UNIT DUCT CAN BE INSTALLED.
2. AERIAL CABLE AND TEMPORARY WOOD POLES SHALL BE REMOVED WHEN PROPOSED LIGHTING IS OPERATIONAL. THE COST SHALL BE INCLUDED IN PAY ITEM REMOVAL OF TEMPORARY LIGHTING UNIT.
3. THE COST FOR REMOVAL OF EXISTING DUCT AND CONDUCTORS (AS REQUIRED BY THE ENGINEER) SHALL BE INCLUDED IN PAY ITEM REMOVAL OF TEMPORARY LIGHTING UNIT.



**MORRIS ENGINEERING, INC.**  
 CONSULTING ENGINEERS  
 1341 Warren Avenue  
 Downers Grove, IL 60515  
 (630) 717-1007 FAX (630) 470-8881  
 www.morrisengineering.com

**AMES Engineering, Inc.**  
 CONSULTING ENGINEERS  
 1341 Warren Avenue  
 Downers Grove, IL 60515  
 (630) 717-1007 FAX (630) 470-8881  
 www.amesengineering.com

LTC-07

FILE NAME = #FILE#	USER NAME = #USER#	DESIGNED - BL	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>CITY OF PALOS HEIGHTS LIGHTING IMPROVEMENTS TEMPORARY / REMOVAL PLAN</b>	F.A.P. R/F.E. = 348	SECTION = 09-00046-00-LT	COUNTY = COOK	TOTAL SHEETS = 20	SHEET NO. = 8	
PLOT SCALE = #SCALE#	CHECKED - SA	REVISED -	SCALE:			SHEET NO. OF SHEETS	STA. TO STA.	<b>CONTRACT NO. 63518</b>			
PLOT DATE = #DATE#	DATE = 06-03-11	REVISED -	ILLINOIS FED. AID PROJECT								