

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE
				BRIDGE 0011
20101000	TEMPORARY FENCE	FOOT	20	20
20101100	TREE TRUNK PROTECTION	EACH	1	1
20101200	TREE ROOT PRUNING	EACH	1	1
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	1	1
20200100	EARTH EXCAVATION	CU YD	2,270	2,270
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1,326	1,326
20300100	CHANNEL EXCAVATION	CU YD	945	945
20400800	FURNISHED EXCAVATION	CU YD	29	29
20800150	TRENCH BACKFILL	CU YD	18	18
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	2,564	2,564
21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	7,782	7,782
25000210	SEEDING, CLASS 2A	ACRE	1.4	1.4
25000310	SEEDING, CLASS 4	ACRE	0.8	0.8
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	198	198
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	198	198
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	198	198
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	7,782	7,782
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	220	220
28000305	TEMPORARY DITCH CHECKS	FOOT	220	220
28000400	PERIMETER EROSION BARRIER	FOOT	2,313	2,313
28000510	INLET FILTERS	EACH	2	2
28100107	STONE RIPRAP, CLASS A4	SQ YD	598	598
28200200	FILTER FABRIC	SQ YD	598	598
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	975	975
40600300	AGGREGATE (PRIME COAT)	TON	13	13
40701801	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 6"	SQ YD	1,948	1,948
42001300	PROTECTIVE COAT	SQ YD	6	6
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	292	292
44000100	PAVEMENT REMOVAL	SQ YD	2,160	2,160
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	276	276
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	637	637
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1
50200100	STRUCTURE EXCAVATION	CU YD	240	240
50300225	CONCRETE STRUCTURES	CU YD	54.7	54.7
50300255	CONCRETE SUPERSTRUCTURE	CU YD	108.4	108.4
50300260	BRIDGE DECK GROOVING	SQ YD	501	501
50300300	PROTECTIVE COAT	SQ YD	590	590
50400705	PRECAST PRESTRESSED CONCRETE DECK BEAMS (42" DEPTH)	SQ FT	3,075	3,075
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	39,550	39,550
51200959	FURNISHING METAL SHELL PILES 14" X 0.312"	FOOT	880	880
51202305	DRIVING PILES	FOOT	880	880
51203200	TEST PILE METAL SHELLS	EACH	2	2

COPYRIGHT © 2011 BY BAXTER & WOODMAN, INC.
 STATE OF ILLINOIS PROFESSIONAL DESIGN FIRM
 No. 184-06-02-0000-0000-0000-0000-0000-0000
 5/6/2011 9:27:30 AM
 ...:\projects\107224\107224.dwg
 H:\C:\ys\107224\107224- Graf Road Bridges\CADD\SURVEY\DRAWINGS\DOCS\PHASE A\Graf West\107224-GrafWest-500.dwg



DESIGNED - CAC	REVISED - 12/30/10 PER MCDOT
DRAWN - BCD	REVISED -
CHECKED - MDW	REVISED -
DATE - 10/08/10	FILE -

MCHENRY COUNTY DIVISION OF TRANSPORTATION
GRAF ROAD BRIDGE OVER
WEST BRANCH PISCASAW CREEK

SUMMARY OF QUANTITIES

SCALE: NONE

STA. TO STA.

TR. RTE. 0037	SECTION 06-00322-01-BR	COUNTY MCHENRY	TOTAL SHEETS 52	SHEET NO. 4
C-91-258-11		CONTRACT NO. 63580	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT BROS-0111064	