



**SCHEDULE OF QUANTITIES**  
INTERCONNECT - U.S. RTE 12-45 (LEE ST) AT PERRY STREET

NO.	QUANT.	UNIT	DESCRIPTION
1.	305	FOOT	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL
2.	1	EACH	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION
3.	350	FOOT	FIBER OPTIC CABLE IN CONDUIT, NO 62.5/125, MM12F SM12F
4.	350	FOOT	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C
5.	1	EACH	DRILL EXISTING HANDHOLE
6.	1	EACH	MODIFY EXISTING CONTROLLER
7.	1	EACH	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2

FILE NAME = 3850-805-TR1.dwg	USER NAME = ZACH WALLSTEN	DESIGNED - CAD	REVISED -	<b>CITY OF DES PLAINES PROPOSED ROADWAY WIDENING AND TRAFFIC SIGNAL INSTALLATION</b>	<b>INTERCONNECT SCHEMATIC</b>	F.A.P. RTE 330	SECTION 10-00213-00-CH	COUNTY COOK	TOTAL SHEETS 47	SHEET NO. 36
PLOT SCALE = 1/101		CHECKED - KLB	REVISED -	SCALE: N.A.		SHEET NO. OF SHEETS		STA. TO STA.		CONTRACT #: 63616
PLOT DATE = 8/23/2011		DATE - 8/23/2011	REVISED -	ILLINOIS FED. AID PROJECT						

GHA #3850.805