

FILE NAME = F:\451-030 75th St D.P.egp DOT\ENGINEERING\DRAWINGS\451-030-sh11-S00.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				75th STREET	
				ROADWAY 0003	TRAFFIC SIGNALS 0021
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	21	21	
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1,648	1,648	
X6020094	MANHOLES, TYPE A, 6' -DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	6	6	
X6020095	MANHOLES, TYPE A, 4' DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	1	1	
X6020294	MANHOLES, TYPE A, 7' -DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	1	1	
X6026050	SANITARY MANHOLES TO BE ADJUSTED	EACH	4	4	
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	20	20	
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
* X7810300	RECESSED REFLECTIVE PAVMENT MARKER	EACH	1,038	1,038	
* X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	1,116		1,116
XX000717	STORM SEWER CONNECTION, SPECIAL	EACH	4	4	
XX008597	TEST HOLE	EACH	75	75	
XX003653	SPECIAL STRUCTURE SP-1	EACH	3	3	
XX005449	AGGREGATE SUBGRADE, 16"	SQ YD	47,831	47,831	
XX007834	SAG FRAME AND LID	EACH	22	22	
Z0007430	TEMPORARY SIDEWALK	SQ FT	1,012	1,012	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	2,238	2,238	
* Z0033046	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2	EACH	2		2
Z0041700	PLUG EXISTING STORM SEWERS	EACH	1	1	
Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	150	150	
Z0056608	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	2,542	2,542	
Z0056610	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	FOOT	304	304	
Z0056612	STORM SEWER (WATER MAIN REQUIREMENTS) 18 INCH	FOOT	82	82	
Z0056614	STORM SEWER (WATER MAIN REQUIREMENTS) 21 INCH	FOOT	327	327	
Z0056616	STORM SEWER (WATER MAIN REQUIREMENTS) 24 INCH	FOOT	602	602	
Z0056622	STORM SEWER (WATER MAIN REQUIREMENTS) 36 INCH	FOOT	209	209	
Z0056624	STORM SEWER (WATER MAIN REQUIREMENTS) 42 INCH	FOOT	25	25	
Z0056626	STORM SEWER (WATER MAIN REQUIREMENTS) 48 INCH	FOOT	17	17	
Z0062456	TEMPORARY PAVEMENT	SQ YD	7,879	7,879	
* Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	12		12
Z0076600	TRAINEES	HOUR	1,000	1,000△	
XX008596	SPECIAL STRUCTURE SP-1, 10' -DIAMETER	EACH	2	2	

\* SPECIALTY ITEMS  
 △ CONSTRUCTION TYPE - CODE 0042



USER NAME = elarson	DESIGNED - GJE	REVISED -
PLOT SCALE = 20.0000' / IN.	DRAWN - DC	REVISED -
PLOT DATE = 9/13/2011	CHECKED - JP	REVISED -
	DATE - 9/08/11	REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
 75TH STREET

SCALE: NONE SHEET NO. 10 OF 198 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0369	07-00232-04-WR	DUPAGE	198	10
CONTRACT NO. 63632			ILLINOIS FED. AID PROJECT	