

FILE NAME = F:\451-030 75th St. DuPage DOT ENGINEERING DRAWINGS\451-030-ahf-schedule.dgn

STAGE	LOCATION STA. - STA.	TEMPORARY PAVEMENT MARKING											
		TEMPORARY PAVEMENT MARKINGS						TEMPORARY MARKING TAPE, TYPE III					
		4" (FT)	6" (FT)	8" (FT)	12" (FT)	24" (FT)	LETTERS & SYMBOLS (SQ FT)	4" (FT)	6" (FT)	8" (FT)	12" (FT)	24" (FT)	LETTERS & SYMBOLS (SQ FT)
STAGE 1	75TH STREET												
	460+00 - 497+00	342	29	588	147	-	36	1,705	259	1,613	412	-	145
	497+00 - 512+00	1,735	-	489	137	-	-	-	-	-	-	-	-
	512+00 - 527+00	1,708	-	-	-	-	-	-	-	-	-	-	-
	527+00 - 542+00	3,661	480	1,488	266	71	145	-	-	-	-	-	-
	542+00 - 557+00	1,531	212	-	-	-	36	-	-	-	-	-	-
	557+00 - 572+00	1,436	-	-	-	-	-	-	-	-	-	-	-
	572+00 - 587+00	859	105	-	-	64	73	352	-	-	-	-	-
LEMONT	1,144	-	-	-	114	-	479	-	-	-	-	-	
STAGE 1A	75TH STREET												
	527+00 - 542+00	-	-	-	-	-	-	-	-	-	-	-	-
	542+00 - 557+00	4,188	1,819	-	-	152	182	-	-	-	-	-	-
	557+00 - 572+00	4,174	637	-	-	-	73	-	-	-	-	-	-
	572+00 - 580+50	-	-	-	-	-	-	459	-	-	-	-	-
LEMONT	2,674	1,188	484	115	243	-	1,289	34	888	201	-	218	
STAGE 1B	75TH STREET												
	527+00 - 542+00	70	18	-	-	-	-	-	-	-	-	-	-
	542+00 - 557+00	300	-	-	-	-	-	-	-	-	-	-	-
	557+00 - 572+00	-	-	-	-	-	-	-	-	-	-	-	-
	572+00 - 580+50	-	-	-	-	-	-	-	-	-	-	-	-
LEMONT	3,639	1,294	-	-	215	145	1,387	25	440	114	25	157	
STAGE 2	75TH STREET												
	460+00 - 497+00	-	-	-	-	-	-	-	-	-	-	-	-
	497+00 - 512+00	716	179	-	-	-	36	-	-	-	-	-	-
	512+00 - 527+00	3,242	299	-	-	-	73	-	-	-	-	-	-
	527+00 - 542+00	3,112	666	914	379	150	36	-	-	-	-	-	-
	542+00 - 557+00	3,199	892	2,148	1,011	176	363	-	-	-	-	-	-
	557+00 - 572+00	4,071	114	766	157	-	109	-	-	-	-	-	-
	572+00 - 580+50	2,380	806	264	160	215	145	-	-	-	-	-	-
LEMONT	2,307	1,024	-	-	98	182	593	281	-	-	-	73	
STAGE 2A	75TH STREET												
	527+00 - 542+00	396	-	-	-	-	-	-	-	-	-	-	-
	542+00 - 557+00	4,286	824	-	-	62	-	-	-	-	-	-	-
	557+00 - 572+00	5,630	436	-	-	-	73	-	-	-	-	-	-
	572+00 - 580+50	1,824	23	521	122	-	36	490	-	-	-	-	-
LEMONT	3,199	687	-	-	99	182	1,962	68	891	194	64	-	
STAGE 2B	75TH STREET												
	527+00 - 542+00	-	-	-	-	-	-	-	-	-	-	-	-
	542+00 - 557+00	759	-	-	-	-	-	-	-	-	-	-	-
	557+00 - 572+00	720	-	-	-	-	-	-	-	-	-	-	-
	572+00 - 580+50	285	-	-	-	-	-	-	-	-	-	-	-
LEMONT	3,113	1,144	484	116	262	-	1,438	25	440	119	88	145	
STAGE 2C	LEMONT	2,734	1,410	-	-	342	254	561	511	892	212	-	-
STAGE 3	460+00 - 497+00	504	1,173	557	133	37	73	504	1,173	557	133	37	73
	497+00 - 512+00	1,853	938	865	267	120	36	2,471	2,308	1,457	351	216	545
	512+00 - 527+00	1,779	528	-	-	-	73	3,533	677	-	-	-	109
	527+00 - 542+00	3,577	1,168	-	-	100	109	3,578	1,312	-	-	125	109
	542+00 - 557+00	3,408	1,628	965	225	143	290	3,408	1,629	965	225	143	290
	557+00 - 572+00	3,805	310	-	-	-	36	3,805	310	-	-	-	36
	572+00 - 580+50	2,348	334	362	49	78	73	2,348	334	362	50	78	145
	LEMONT	840	3,168	-	-	272	507	958	3,539	-	-	331	508
TOTAL	87,548	23,533	10,895	3,284	3,013	3,376	31,320	12,485	8,505	2,011	1,107	2,553	

LOCATION STA. - STA.	PROPOSED PAVEMENT MARKING												
	THERMOPLASTIC PAVEMENT						POLYUREATHANE PAVEMENT				RECESSED REFLEC. MARKERS (EACH)		
	MARKING LINE					LETTERS & SYMBOLS (SQ FT)	MARKING LINE			LETTERS & SYMBOLS (SQ FT)			
4" (FT)	6" (FT)	12" (FT)	24" (FT)	24" (FT)	4" (FT)		6" (FT)	24" (FT)	LETTERS & SYMBOLS (SQ FT)				
75TH STREET													
490+00 - 497+00	1,700.0	1,516.0	-	-	36.0	109.2	-	-	-	-	-	-	85
497+00 - 512+00	3,922.5	2,469.0	1,841.8	241.8	309.7	473.2	-	-	-	-	-	-	182
512+00 - 527+00	4,038.0	781.4	2,203.3	829.1	122.1	218.4	-	-	-	-	-	-	112
527+00 - 542+00	3,851.0	768.7	2,395.5	1,626.8	158.7	291.2	-	-	-	-	-	-	178
542+00 - 557+00	4,080.0	2,493.0	-	-	274.6	400.4	-	-	-	-	-	-	177
557+00 - 572+00	4,334.5	1,024.8	-	-	102.2	72.8	-	-	-	-	-	-	93
572+00 - 580+50	1,910.0	365.8	657.7	343.8	98.4	218.4	-	-	-	-	-	-	70
LEMONT	3,537.3	3,031.0	-	-	273.4	509.6	64.0	565.0	37.0	109.0	-	-	109
WOODWARD	849	906.4	-	-	43	145.6	-	-	-	-	-	-	32
TOTAL	28,222.3	13,356.1	7,098.3	3,041.5	1,418.1	2,438.8	64.0	565.0	37.0	109.0	-	-	1,038.0

LOCATION STA. - STA.	COMBINATION CONCRETE CURB & GUTTER				
	TYPE				
	B-6.12 (FT)	B-6.18 (FT)	B-6.24 (FT)	B-9.12 (FT)	TYPE B (FT)
75TH STREET					
490+00 - 497+00	-	-	1080	1110	-
497+00 - 512+00	-	50	3030	2550	-
512+00 - 527+00	610	50	3350	2510	-
527+00 - 542+00	220	-	2920	2610	-
542+00 - 557+00	445	-	3130	2980	190
557+00 - 572+00	865	-	855	810	-
572+00 - 580+50	185	-	2100	440	-
LEMONT	205	-	0	0	150
TOTAL	2530	100	16465	13010	340

LOCATION STA. - STA.	MEDIANS	
	TYPE	
	SB-9.12 (SQ. YD)	HMA MEDIAN (SQ. YD)
75TH STREET		
490+00 - 497+00	-	-
497+00 - 512+00	-	-
512+00 - 527+00	-	133.3
527+00 - 542+00	-	143.2
542+00 - 557+00	-	115.2
557+00 - 572+00	-	-
572+00 - 580+50	-	-
LEMONT	7,139.0	-
TOTAL	7,139.0	391.8

LOCATION STA. - STA.	PCC SIDEWALK 5"
	QUANTITY (SQ FT)
75TH STREET	
490+00 - 497+00	-
497+00 - 512+00	-
512+00 - 527+00	-
527+00 - 542+00	1,578
542+00 - 557+00	3,541
557+00 - 572+00	515
572+00 - 580+50	220
LEMONT	1,657
WOODWARD	-
TOTAL	7,511.4

NOTE: BASIS OF MEASUREMENT AND PAYMENT PER STANDARD SPECIFICATIONS, SUPPLEMENTAL SPECIFICATIONS, AND RECURRING SPECIAL PROVISIONS UNLESS MARKED IN THE MARGIN WITH "SPL" WHICH IDENTIFIES THOSE ITEMS WHICH ARE RULED BY SECTIONS OF THE CONTRACT SPECIAL PROVISIONS.



USER NAME = alarson	DESIGNED - GJE	REVISED -
PLOT SCALE = 50.0000' / IN.	DRAWN - DC	REVISED -
PLOT DATE = 9/13/2011	CHECKED - JP	REVISED -
	DATE - 9/08/11	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES	
75TH STREET	
SCALE:	SHEET NO. 14 OF 198 SHEETS
STA.	TO STA.

F.A.P. RTE. 0369	SECTION 07-00232-04-WR	COUNTY DuPAGE	TOTAL SHEETS 198	SHEET NO. 14
CONTRACT NO. 63632			ILLINOIS FED. AID PROJECT	