



LOCATION STA. TO STA.	LANDSCAPING			FERTILIZER (SODDING RATE 60 LBS/ACRE)			
	TOPSOIL FURNISH AND PLACE 6" (SQ. YD)	SODDING, SALT TOLERANT (SQ. YD)	SODDING (SQ YD)	SUPPLEMENTAL WATERING (UNIT)	NITROGEN FERTILIZER NUTRIENT (POUND)	PHOSPHOROUS FERTILIZER NUTRIENT (POUND)	POTASSIUM FERTILIZER NUTRIENT (POUND)
STA. 557+54 TO STA. 572+00	---	3323	9227	126	155	155	155
STA. 572+00 TO STA. 576+11.40	---	2182	1807	29	50	50	50

NOTE: SODDING, SALT-TOLERANT IS TO BE USED IN THE MEDIANS AND WITHIN 10 FEET FROM THE BACK OF CURB. SODDING WILL BE USED IN ALL OTHER LOCATIONS.



USER NAME = gellwanger	DESIGNED - GJE	REVISED -
PLOT SCALE = 50.0000' / 1" IN.	DRAWN - DC	REVISED -
PLOT DATE = 9/7/2011	CHECKED - JP	REVISED -
	DATE - 9/08/11	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PAVMENT MARKING AND LANDSCAPING PLAN
75TH STREET

SCALE: 1"=50' SHEET NO. 98 OF 198 SHEETS STA. 557+00 TO STA. 587+00

F.A.P. RTE. 0369	SECTION 07-00232-04-WR	COUNTY DUPAGE	TOTAL SHEETS 198	SHEET NO. 98
CONTRACT NO. 63632				ILLINOIS FED. AID PROJECT

FILE NAME = F:\451-638-75th st. dupage. det\engineering\drwg\75th-038-ahh.pmk-1.indd.p.dgn