

GIRDER 10 (CONT)				
LOCATION	STATION	OFFSET	THEORETICAL GRADE ELEVATION	ELEVATIONS ADJUSTED FOR DEAD LOAD DEFLECTION
BA	729+81.00	36.00	649.12	649.15
BB	729+91.00	36.00	649.17	649.18
CLP4	729+97.50	36.00	649.21	649.21
BC	730+07.50	36.00	649.26	649.26
BD	730+17.50	36.00	649.31	649.32
BE	730+27.50	36.00	649.36	649.39
BF	730+37.50	36.00	649.41	649.46
BG	730+47.50	36.00	649.46	649.52
BH	730+57.50	36.00	649.51	649.58
BJ	730+67.50	36.00	649.56	649.62
BK	730+77.50	36.00	649.61	649.65
BL	730+87.50	36.00	649.66	649.69
BM	730+97.50	36.00	649.71	649.72
BN	731+07.50	36.00	649.76	649.75
CLP5	731+20.50	36.00	649.82	649.82
BP	731+30.50	36.00	649.87	649.90
BQ	731+40.50	36.00	649.92	649.98
BR	731+50.50	36.00	649.97	650.07
BS	731+60.50	36.00	650.02	650.16
BT	731+70.50	36.00	650.05	650.23
BU	731+80.50	36.00	650.07	650.27
BV	731+90.50	36.00	650.08	650.29
BW	732+00.50	36.00	650.08	650.27
BX	732+10.50	36.00	650.06	650.23
BY	732+20.50	36.00	650.02	650.16
BZ	732+30.50	36.00	649.97	650.07
CA	732+40.50	36.00	649.91	649.97
CB	732+50.50	36.00	649.84	649.86
CLP6	732+57.00	36.00	649.78	649.78
CC	732+67.00	36.00	649.68	649.67
CD	732+77.00	36.00	649.57	649.56
CE	732+87.00	36.00	649.44	649.44
CF	732+97.00	36.00	649.30	649.31
CG	733+07.00	36.00	649.15	649.16
CH	733+17.00	36.00	648.98	648.99
CJ	733+27.00	36.00	648.80	648.81
CK	733+37.00	36.00	648.60	648.60
CL	733+47.00	36.00	648.39	648.38
CM	733+57.00	36.00	648.17	648.16
CLP7	733+70.00	36.00	647.86	647.86
CN	733+80.00	36.00	647.60	647.64
CP	733+90.00	36.00	647.33	647.41
CQ	734+00.00	36.00	647.05	647.17
CR	734+10.00	36.00	646.75	646.91
CS	734+20.00	36.00	646.44	646.63
CT	734+30.00	36.00	646.12	646.32
CU	734+40.00	36.00	645.78	645.98
CV	734+50.00	36.00	645.43	645.60
CW	734+60.00	36.00	645.06	645.19
CX	734+70.00	36.00	644.68	644.75
CLBRGN	734+80.63	36.00	644.26	644.26
BKNABUT	734+84.38	36.00	644.11	644.11

FILE NAME =
D264B80-shr-scr-eccl.dgn

USER NAME = dwoznjarski

DESIGNED - ACB

REVISED -

CHECKED - JMB

REVISED -

PLOT SCALE = 1/8" = 1' / IN.

DRAWN - RLK

REVISED -

PLOT DATE = 7/18/2011

CHECKED - ACB

REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

DECK ELEVATIONS - SHEET 8
STRUCTURE NO. 098-0115

SHEET NO. 23 OF 103 SHEETS

F.A.P.
RTE.
646

SECTION
IB-2

COUNTY
WHITESIDE

TOTAL SHEETS
257

SHEET NO.
126

CONTRACT NO. 64B80

ILLINOIS FED. AID PROJECT