

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	80% FED./20% STATE		
			TOTAL QUANTITY	ROADWAY 0004 RURAL	BRIDGE 0011 S.N. 071-0097
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	629	629	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	56	56	
20200100	EARTH EXCAVATION	CU YD	1250	1250	
20400800	FURNISHED EXCAVATION	CU YD	7880	7880	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	13713	13713	
* 25000210	SEEDING, CLASS 2A	ACRE	2	2	
* 25000310	SEEDING, CLASS 4	ACRE	1	1	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	270	270	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	270	270	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	270	270	
** 25000750	MOWING	ACRE	2	2	
* 25100115	MULCH, METHOD 2	ACRE	3	3	
25100630	EROSION CONTROL BLANKET	SQ YD	8654	8654	
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	4407	4407	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1079	1079	
28000305	TEMPORARY DITCH CHECKS	FOOT	98	98	
28000400	PERIMETER EROSION BARRIER	FOOT	3519	3519	
28000500	INLET AND PIPE PROTECTION	EACH	2	2	
28100107	STONE RIPRAP, CLASS A4	SQ YD	78	78	
28200200	FILTER FABRIC	SQ YD	78	78	
31100200	SUBBASE GRANULAR MATERIAL, TYPE A	CU YD	3284	3284	
31100910	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	2237	2237	
42000411	PORTLAND CEMENT CONCRETE PAVEMENT 9 1/2" (JOINTED)	SQ YD	4963	4963	
42001200	PAVEMENT FABRIC	SQ YD	4963	4963	
42001300	PROTECTIVE COAT	SQ YD	10756	10756	
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	980	980	
44000100	PAVEMENT REMOVAL	SQ YD	1514	1514	
44004250	PAVED SHOULDER REMOVAL	SQ YD	577	577	
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	156	156	
48300100	PORTLAND CEMENT CONCRETE SHOULDERS 6"	SQ YD	653	653	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50157300	PROTECTIVE SHIELD	SQ YD	500		500
50200100	STRUCTURE EXCAVATION	CU YD	821		821

* SPECIALTY ITEM
** 100% STATE FUNDING