

ITEM 70400100 TEMPORARY CONCRETE BARRIER		
LOCATION STATION TO STATION	LENGTH (FOOT)	COMMENT
IL 2		
514+36.24 TO 523+62.20	937.5	STAGE 1A
TOTAL	937.5	

ITEM 70400200 RELOCATE TEMPORARY CONCRETE BARRIER		
LOCATION STATION TO STATION	LENGTH (FOOT)	COMMENT
IL 2		
514+36.26 TO 520+64.00	637.5	STAGE 1B
521+54.94 TO 523+76.33	225.0	STAGE 1B
506+11.00 TO 514+86.13	912.5	STAGE 2A
506+11.00 TO 514+86.13	912.5	STAGE 2B
509+13.39 TO 518+73.93	962.5	STAGE 3A
509+13.41 TO 519+12.50	1000.0	STAGE 3B
TOTAL	4650.0	

ITEM X7800610 URETHANE PAVEMENT MARKING - LINE 4"			
LOCATION STATION TO STATION	OFFSET	LENGTH (FOOT)	COMMENT
IL 2			
504+53.48 TO 520+80.00	LT	1626	SOLID WHITE
504+53.48 TO 524+90.00	RT	2037	SOLID WHITE
504+53.48 TO 524+75.00	RT	2022	SOLID YELLOW MEDIAN
517+47.92 TO 522+75.97	RT	529	SOLID YELLOW MEDIAN
517+47.92 TO 522+75.97	LT	529	SOLID YELLOW MEDIAN
512+35.58 TO 524+75.00	LT	1239	SOLID YELLOW MEDIAN
504+53.48 TO 512+35.58	LT	195	YELLOW SKIP DASH 30'-10'
TOTAL		8177	

ITEM X7800640 URETHANE PAVEMENT MARKING - LINE 8"			
LOCATION STATION TO STATION	OFFSET	LENGTH (FOOT)	COMMENT
IL 2			
520+75.00 521+95.00	RT	30	WHITE SKIP DASH 6'-2'
520+75.00 522+75.00	RT	50	WHITE SKIP DASH 6'-2'
521+95.00 524+89.50	RT	295	SOLID WHITE
522+75.00 524+89.50	RT	215	SOLID WHITE
525+78.00 526+73.00	LT	98	SOLID WHITE
TOTAL		688	

ITEM X7800650 URETHANE PAVEMENT MARKING - LINE 12"		
LOCATION STATION TO STATION	LENGTH (FOOT)	COMMENT
IL 2		
517+47.92 TO 524+75.50	129	SOLID YELLOW MEDIAN
TOTAL	129	

ITEM X7800680 URETHANE PAVEMENT MARKING - LINE 24"			
LOCATION STATION TO STATION	OFFSET	LENGTH (FOOT)	COMMENT
IL 2			
524+75.00	RT/LT	12	SOLID WHITE
524+89.50	RT	40	SOLID WHITE
525+78.00	LT	14	SOLID WHITE
525+85.00	LT/RT	14	SOLID WHITE
TOTAL		80	

ITEM 78100100 RAISED REFLECTIVE PAVEMENT MARKER		
LOCATION STATION TO STATION	(EACH)	COMMENT
IL 2		
504+00.00 511+89.37	10	TWO WAY AMBER
517+59.37 522+89.66	26	ONE WAY AMBER
521+95.00 524+89.50	8	ONE WAY CRYSTAL
522+75.00 524+75.50	6	ONE WAY CRYSTAL
525+78.00 526+73.00	3	ONE WAY CRYSTAL
TOTAL	53	

ITEM 78200410 GUARDRAIL MARKERS, TYPE A		
LOCATION STATION TO STATION	OFFSET	(EACH)
IL 2		
504+86.23 TO 513+04.37	RT	6
516+44.37 TO 522+62.24	RT	8
511+11.23 TO 513+04.37	LT	4
516+44.37 TO 519+25.02	LT	4
TOTAL		22

ITEM 78200520 BARRIER WALL MARKERS, TYPE B		
LOCATION STATION TO STATION	OFFSET	(EACH)
IL 2		
513+04.37 TO 516+44.37	RT	5
513+04.37 TO 516+44.37	LT	5
TOTAL		10

ITEM 78201000 TERMINAL MARKER - DIRECT APPLIED		
LOCATION STATION TO STATION	OFFSET	(EACH)
IL 2		
504+86.23	RT	1
511+11.23	LT	1
519+25.02	LT	1
522+62.24	RT	1
TOTAL		4

ITEM 78300100 PAVEMENT MARKING REMOVAL			
LOCATION STATION TO STATION	OFFSET	AREA (SQ FT)	COMMENT
IL 2			
504+53.48 520+80.00	LT	542.00	SOLID WHITE
504+53.48 524+90.00	RT	678.84	SOLID WHITE
504+53.48 524+75.00	RT	673.84	SOLID YELLOW MEDIAN
517+47.92 522+75.97	RT	176.33	SOLID YELLOW MEDIAN
517+47.92 522+75.97	LT	176.33	SOLID YELLOW MEDIAN
512+35.58 524+75.00	LT	413.00	SOLID YELLOW MEDIAN
504+53.48 512+35.58	LT	65.17	YELLOW SKIP DASH 30'-10'
522+69.00 524+88.00	RT	146.00	SOLID WHITE
522+69.00 524+88.00	RT	146.00	SOLID WHITE
525+78.00 526+73.00	LT	65.33	SOLID WHITE
520+80.00 522+69.00	RT	31.50	WHITE SKIP DASH 6'-2'
520+80.00 522+69.00	RT	31.50	WHITE SKIP DASH 6'-2'
517+47.92 522+75.97		114.00	SOLID YELLOW MEDIAN
524+75.00	LT/RT	24.00	SOLID WHITE
524+90.00	RT	80.00	SOLID WHITE
525+78.00	LT	28.00	SOLID WHITE
525+85.00	LT/RT	28.00	SOLID WHITE
TOTAL		3420	

ITEM Z0004638 PAVEMENT BREAKING	
LOCATION STATION TO STATION	AREA (SQ YD)
IL 2	
509+91.93 TO 512+89.37	1481
516+07.00 TO 520+93.41	2684
TEMPORARY PAVEMENT	
511+13.74 TO 513+46.58	1139
515+77.06 TO 517+19.72	698
TOTAL	6002

ITEM Z0062456 TEMPORARY PAVEMENT			
LOCATION STATION TO STATION	OFFSET	AREA (SQ YD)	COMMENT
IL 2			
510+52.01 TO 513+45.68	RT	720	STAGE 2A
510+52.01 TO 513+45.68	LT	720	STAGE 2B
515+77.06 TO 517+86.43	RT	512	STAGE 1A
515+77.06 TO 517+86.43	LT	512	STAGE 1B
LOCATION AS DIRECTED BY ENGINEER		111	
TOTAL		2575	

ITEM X4400110 TEMPORARY PAVEMENT REMOVAL			
LOCATION STATION TO STATION	OFFSET	AREA (SQ YD)	COMMENT
IL 2			
510+52.01 TO 511+13.74	RT	151	STAGE 2A
510+52.01 TO 511+13.74	LT	151	STAGE 2B
517+19.72 TO 517+86.43	RT	163	STAGE 1A
517+19.72 TO 517+86.43	LT	163	STAGE 1B
LOCATION AS DIRECTED BY ENGINEER		111	
TOTAL		739	

ITEM Z0025500 FURNISHING AND INSTALLING PROPERTY MARKERS		
LOCATION STATION TO STATION	OFFSET	(EACH)
IL 2		
512+81.60	125.52 RT	1
TOTAL		1