

# SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	80% FED./20% STATE		
			TOTAL QUANTITY	ROADWAY 0004 RURAL	BRIDGE 0011 S.N. 071-0096
50200100	STRUCTURE EXCAVATION	CU YD	292.9		292.9
50300100	FLOOR DRAINS	EACH	6		6
50300225	CONCRETE STRUCTURES	CU YD	450.2		450.2
50300255	CONCRETE SUPERSTRUCTURE	CU YD	621.3		621.3
50300260	BRIDGE DECK GROOVING	SQ YD	1726		1726
50300280	CONCRETE ENCASEMENT	CU YD	23.1		23.1
50300300	PROTECTIVE COAT	SQ YD	2098		2098
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1
50500505	STUD SHEAR CONNECTORS	EACH	6102		6102
50800105	REINFORCEMENT BARS	POUND	60	60	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	191620		191620
50800515	BAR SPLICERS	EACH	1653		1653
51100100	SLOPE WALL 4 INCH	SQ YD	39		39
51201800	FURNISHING STEEL PILES HP14X73	FOOT	2410		2410
51202305	DRIVING PILES	FOOT	2410		2410
51203800	TEST PILE STEEL HP14X73	EACH	5		5
51500100	NAME PLATES	EACH	1		1
52100520	ANCHOR BOLTS, 1"	EACH	60		60
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1	
54215547	METAL END SECTIONS 12"	EACH	6	6	
54248510	CONCRETE COLLAR	CU YD	1.3	1.3	
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	3	3	
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	12	12	
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	24	24	
55100500	STORM SEWER REMOVAL 12"	FOOT	173	173	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	86		86
60100945	PIPE DRAINS 12"	FOOT	362	362	
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1	
60500040	REMOVING MANHOLES	EACH	1	1	
60500060	REMOVING INLETS	EACH	4	4	
60600605	CONCRETE CURB, TYPE B	FOOT	868	868	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	320	320	

\* SPECIALTY ITEM  
\*\* 100% STATE FUNDING